

# NEWEA Annual Conference

January 26, 2015

You Want to Put What? Where? – Old Saybrook's Decentralized Hybrid Approach For Their Shorefront Community

## Outline

- Background Regulatory Requirements **Program Status** AT Challenges Cluster System Evaluations Community System **Evaluations**
- What's Next





## Background


Wastewater Issues
TMDL for nitrogen into Long Island Sound
High Density Development
4 to 8 homes per acre
Older systems (50+ years old) built prior to current Public Health Code (PHC)
High groundwater table
Highly permeable or

 Highly permeable of unsuitable soils





#### The Frequency of Hypoxia in Long Island Sound Bottom Waters\*




\*Courtesy of CT Department of Energy and Environmental Protection 2013



## Background

Wastewater Management District Established

> 15 Focus Areas 1,900 Properties






## Background

- August 2009 Citizens Approve Decentralized Referendum
  - \$41M program (vs \$72M centralized "Big Pipe" program) 8 Year duration
  - Adopted Wastewater Management District Ordinance



#### Conventional Shorefront Septic System Problems




The Treatment Occurs In The Unsaturated Soil!



## Regulatory Requirements Within the WWMD

- Cesspools removed and replaced
  - Septic tanks upgraded to PHC; add effluent filters
- Leaching systems upgraded to extent possible:
  - Between 2/3 and 100% of area required by PHC
  - Replace deep drywells with shallower systems
- Alternative Technology (AT) required for N removal:
  - All "Water Proximity" lots
  - When leaching field can not be upgraded to 2/3 PHC area



WWW.SKYPIC.COM




#### Old Saybrook WWMD Program - Financing

#### Financial

- 25% Clean Water Fund (CWF) Grant, 75% Loan Project
- 25% Local Contributions
- 50% Benefit Assessments to End Users


Upgrade Program Finance Plan





### Program Status

Phase I – Conventional Systems Portion
13 Contracts have been awarded – 285 lots in 6 Focus Areas
AT Implementation Proceeding





AT Systems for Water Proximity Lots CTDEEP Finalizing AT Delegation

Document

Review and approval authority for AT systems to OSWPCA - currently resembles NPDES permit

 AT Equipment Preselection – No Pre-approved "Black Boxes"

- AT Management Policies

Corrective Action Triggers

 19 mg/l median or 38 mg/l discrete sample

Responsibility for Maintenance



## Challenges to AT Systems

More Challenging Lots
 Increased Cost/Lot

Climate Change and Sea Level Rise

Individual Lot Testing/ Design

- Multiple Agency Reviews (local & DEEP)
- Aesthetics
- Seasonal Occupation



"Goodbye Sandy, Goodnight Irene"



#### What Are Some Alternatives? Cluster and/or Community Systems

DEEP Regulated

• 21 Day Travel Time

No credit for UV Disinfection

Mounding Analysis

- Unsaturated depth min. 3 feet

N-Removal (10 mg/l at Point of Env. Concern)


• 1.2 gpd/sf Loading Rate with Pretreatment

P-Removal Soil Capacity (6 months)

Individual Permits



# Wastewater Systems – Cluster / Community



NOTE: 21 Day Travel Time to Nearest Sensitive Receptor Required


f FUSS&O'NEILL

Step 1 – Clusters Within/Adjacent to Focus Areas


- Desktop Evaluation of Phase II Areas
  - Great Hammock Beach
  - Indiantown
  - Ingham Hill
  - Meadowood



### Great Hammock Beach




#### SUBSURFACE CONDITIONS



#### Subsurface data points from:

- •1) CRAHD on-site test pit records
- •2) Spring 2002 GW Monitoring report by Cummins Envirotech, Inc.





### Indiantown

Subsurface data points from:

1) CRAHD on-site test pit records

2) Spring 2002 GW Monitoring report by Cummins Envirotech, Inc.

#### SUBSURFACE CONDITIONS

Subsurface Data Point
 Study Area Boundary
 Subsurface Sewage Disposal Potential
 High Potential
 Medium Potential
 Low Potential
 Very Low Potential
 Extremely Low Potential
 Fill Soils - Not Rated



# Ingham Hill


#### SUBSURFACE CONDITIONS

- Subsurface Data Point
   Study Area Boundary
   Subsurface Sewage Disposal Potential
   High Potential
   Medium Potential
   Low Potential
   Very Low Potential
  - Extremely Low Potential Fill Soils - Not Rated


Subsurface data points from:

1) CRAHD on-site test pit records

•2) Spring 2002 GW Monitoring report by Cummins Envirotech, Inc.



#### Meadowood




## Great Hammock Beach – Evaluated Sites





### Indiantown – Evaluated Sites






# Ingham Hill – Evaluated Sites





## Meadowood – Evaluated Sites





# Ingham Hill – Site ING1



FUSS&O'NEILL


# Ingham Hill – Site ING1





### Desktop Evaluations of 19 Sites

#### 8 pages of calculations per site x 19 Sites = a lot of number crunching!



FUSS&O'NEILL

## Great Meadow Beach – Site G1






# Great Meadow Beach – Site G1

Depth to Restrictive Layer:	13	inches (ba	sed on near	by testing)	
USDA / CT DEEP Soil Suitability for Septic Systems:	Fill Soils -	Not Rated			MERTING SER
Notable Site Features					
	e required				
					at the second second
	ards to serv	/e 10 3-bec	lrooms hou	JSES	Carlo alle alle
with pretreatment and 12.7 feet of engineered fill.					IT - Y
1. Summary of Calculations					· LE · Kine ·
	10.0 to 15	0 ft / day			Frank and the
	10.0 10 13.	0 it / uay			O CEN
Design Flow (includes 1.5 factor of safety) =	4 500	aal / dav			
					a the set
			- day		C. Carso
		<b>U</b>			2 Call Cape
Leaching System Type = Tandem ADS Arc 24 F	lastic Cham	nbers w/ Ap	proved Stor	ie	Chies 2
					3
· · ·		• •			
			per Row		
Effective Leaching Area Provided =	7,990	sq. ft			
Regulatory Condition	Required	Actual	Units	Status	
Total Leaching System Capacity =	4,500		gal / day	PASS	
	216	235	lin. ft.	PASS	
Unsaturated Soil Depth for Effluent Renovation =	3.0		ft.	PASS	
			gpd	PASS	
			days		
			-		
Phosphorus Removal Modeling =	6.0	6.1	months	PASS	
Nata: All regulatory conditions must be esticified prior to incurrent			for a alucto		
note. An regulatory conditions must be satisfied prof to ISSUAR			ior a cluste	system.	
Based on CT DEP February 2006 "Guidance for Design of Large-S	cale On-Site	Wastewate	Renovation	Svstems"	
					FUSS&O'NEII
	USDA / CT DEEP Soil Suitability for Septic Systems: Notable Site Features: Site ground elevation = 4.0 based on CT DEEP LiDAR data. Groundwater Depth = 13" Leaching field constructed in 12.7 feet of engineered fill would b Appears possible to site a leaching system to DEEP stands with pretreatment and 12.7 feet of engineered fill. 1. Summary of Calculations Permeability of Soils = Design Flow (includes 1.5 factor of safety) = Wastewater Strength = Long Term Acceptance Rate = Leaching System Type = Tandem ADS Arc 24 P Number or Leaching System Rows = Length per Row of Leaching System = Effective Leaching System Capacity = Linear Loading Rates (GW Mounding) = Unsaturated Soil Depth for Effluent Renovation = Soil Capacity for Vertical Movement of Effluent = 21 Day Travel Time of Effluent = Nitrogen Dilution Modeling = Phosphorus Removal Modeling = Note: All regulatory conditions must be satisfied prior to issuan	USDA / CT DEEP Soil Suitability for Septic Systems: Fill Soils - Notable Site Features: Site ground elevation = 4.0 based on CT DEEP LiDAR data. Groundwater Depth = 13" Leaching field constructed in 12.7 feet of engineered fill would be required Appears possible to site a leaching system to DEEP standards to serwith pretreatment and 12.7 feet of engineered fill.  Appears possible to site a leaching system to DEEP standards to serwith pretreatment and 12.7 feet of engineered fill.  Design Flow (includes 1.5 factor of safety) = 4,500 Wastewater Strength = Residentia Long Term Acceptance Rate = 1.20 Leaching System Type = Tandem ADS Arc 24 Plastic Cham Number or Leaching System Rows = 4 Length per Row of Leaching System Rows = 235 Effective Leaching System Capacity = 4,500 Linear Loading Rates (GW Mounding) = 216 Unsaturated Soil Depth for Effluent Renovation = 3,0 Soil Capacity for Vertical Movement of Effluent = 4,500 21 Day Travel Time of Effluent = 21.0 Nitrogen Dilution Modeling = 6,0 Note: All regulatory conditions must be satisfied prior to issuance of CT DE	USDA / CT DEEP Soil Suitability for Septic Systems: Fill Soils - Not Rated Notable Site Features: Site ground elevation = 4.0 based on CT DEEP LiDAR data. Groundwater Depth = 13" Leaching field constructed in 12.7 feet of engineered fill would be required Appears possible to site a leaching system to DEEP standards to serve 10 3-bec with pretreatment and 12.7 feet of engineered fill.  1. Summary of Calculations Permeability of Soils = 10.0 to 15.0 ft / day Design Flow (includes 1.5 factor of safety) = 4,500 gal / day Wastewater Strength = Residential Long Term Acceptance Rate = 1.20 gal / sq. ft Leaching System Type = Tandem ADS Arc 24 Plastic Chambers w/ Ap Number or Leaching System Rows = 4 row(s) Length per Row of Leaching System 235 linear feet t Effective Leaching Area Provided = 7,990 sq. ft Regulatory Condition Required Actual Total Leaching System Capacity = 4,500 9,588 Linear Loading Rates (GW Mounding) = 216 235 Unsaturated Soil Depth for Effluent Renovation = 3.0 3.8 Soil Capacity for Vertical Movement of Effluent = 4,500 210,936 21 Day Travel Time of Effluent = 21.0 40.9 Note: All regulatory conditions must be satisfied prior to issuance of CT DEEP permit	USDA / CT DEEP Soil Suitability for Septic Systems: Fill Soils - Not Rated Notable Site Features: Site ground elevation = 4.0 based on CT DEEP LiDAR data. Groundwater Depth = 13" Leaching field constructed in 12.7 feet of engineered fill would be required Appears possible to site a leaching system to DEEP standards to serve 10 3-bedrooms hou with pretreatment and 12.7 feet of engineered fill.  Appears possible to site a leaching system to DEEP standards to serve 10 3-bedrooms hou with pretreatment and 12.7 feet of engineered fill.  Design Flow (includes 1.5 factor of safety) = 4,500 gal / day Wastewater Strength = Residential Long Term Acceptance Rate = 1.20 gal / sq. ft - day Leaching System Type = Tandem ADS Arc 24 Plastic Chambers w/ Approved Stor Number or Leaching System Rows = 4 row(s) Length per Row of Leaching System = 235 linear feet per Row Effective Leaching Area Provided = 7,990 sq. ft Regulatory Condition Required Actual Units Unsaturated Soil Depth for Effluent Renovation = 3.0 3.8 ft. Soil Capacity for Vertical Movement of Effluent = 21.0 4.0.9 days Nitrogen Dilution Modeling = 10.00 1.88 mg/L Phosphorus Removal Modeling = 6.0 6.1 months Note: All regulatory conditions must be satisfied prior to issuance of CT DEEP permit for a cluster	USDA / CT DEEP Soil Suitability for Septic Systems: Fill Soils - Not Rated Notable Site Features: Site ground elevation = 4.0 based on CT DEEP LiDAR data. Groundwater Depth = 13" Leaching field constructed in 12.7 feet of engineered fill would be required Appears possible to site a leaching system to DEEP standards to serve 10 3-bedrooms houses with pretreatment and 12.7 feet of engineered fill.  Appears possible to site a leaching system to DEEP standards to serve 10 3-bedrooms houses with pretreatment and 12.7 feet of engineered fill.  Appears possible to site a leaching system to DEEP standards to serve 10 3-bedrooms houses with pretreatment and 12.7 feet of engineered fill.  Appears possible to site a leaching system to for the serve 10 3-bedrooms houses with pretreatment and 12.7 feet of engineered fill.  Appears possible to site a leaching system to for the serve 10 3-bedrooms houses with pretreatment and 12.7 feet of engineered fill.  Appears possible to site a leaching system to for the serve 10 3-bedrooms houses with pretreatment and 12.7 feet of engineered fill.  Appears possible to site a leaching system to for the serve 10 3-bedrooms houses with pretreatment and 12.7 feet of engineered fill.  Appears possible to site a leaching setwater Strength = Residential Long Term Acceptance Rate = 1.20 gal / sq. ft - day Leaching System Type = Tandem ADS Arc 24 Plastic Chambers w/ Approved Stone Number or Leaching System Rows = 4 row(s) Length per Row of Leaching System = 235 linear feet per Row Effective Leaching Area Provided = 7,990 sq. ft Regulatory Condition Required Actual Units Status Cold Leaching System Capacity = 4,500 9,588 gal / day PASS Unsaturated Soil Depth for Effluent Renovation = 3.0 3.8 ft. PASS Soil Capacity for Vertical Movement of Effluent = 4,500 210,936 gpd PASS Soil Capacity for Vertical Movement of Effluent = 21.0 40.9 days PASS Nitrogen Dilution Modeling = 10.00 1.88 mg/L PASS

## Great Meadow Beach – Site



Notable Site Features:

Site ground elevation = 4.0 based on CT DEEP LiDAR data.

Groundwater Depth = 13"

ered Leaching field constructed in 12.7 feet of engineered fill would be required

Appears possible to site a leaching system to DEEP standards to with pretreatment and 12.7 feet of engineered fill.

#### 1. Summary of Calculations

Permeability of S

Design Flow (includes 1.5 factor

Waste Long Term

Leaching System Type

Nur l e

echired

	Required	Actual	Units	Status
_apacity =	4,500	9,588	gal / day	PASS
. Mounding) =	216	235	lin. ft.	PASS
ent Renovation =	3.0	3.8	ft.	PASS
<pre>Jvement of Effluent =</pre>	4,500	210,936	gpd	PASS
ravel Time of Effluent =	21.0	40.9	days	PASS
<pre>itrogen Dilution Modeling =</pre>	10.00	1.88	mg/L	PASS
.osphorus Removal Modeling =	6.0	6.1	months	PASS

1. ft - day

Jers w/ Approved Stone

4 row(s)

7,990 sq. ft

235 linear feet per Row

.ons must be satisfied prior to issuance of CT DEEP permit for a cluster system.



d)

ebruary 2006 "Guidance for Design of Large-Scale On-Site Wastewater Renovation Systems"

Νc

### Results of Cluster System Desktop Evaluations

Locati	on	Technically Feasible	'Real World' Potential	SWAS Capacity	Comments
	G1	YES	UNLIKELY	10 homes	12.7 ft of fill required
	G2	NO	NO	-	Fails 21-day bacteria travel time
Great Hammock	G3	NO	NO	-	Fails 21-day bacteria travel time
Beach	G4	NO	NO	-	Fails 21-day bacteria travel time
	G5	NO	NO	-	Fails 21-day bacteria travel time
	G6	NO	NO	-	Fails 21-day bacteria travel time
	IND1	YES	UNLIKELY	17 homes	8.9 ft of fill required
	IND2	NO	NO	-	Fails 21-day bacteria travel time
	IND3	NO	NO	-	Fails 21-day bacteria travel time
	IND4	YES	NO	1 home	Supports a 4-bedroom home
Indiantown	IND5	NO	NO	-	Fails 21-day bacteria travel time
	IND6	YES	NO	1 home	Supports a 2-bedroom home
	IND7	YES	NO	1 home	Supports a 2-bedroom home
	IND8	NO	NO	-	Fails 21-day bacteria travel time
	IND9	NO	NO	-	Fails 21-day bacteria travel time
Ingham Hill	ING1	YES	VERY LIKELY	33 homes	Need detailed subsurface investigation
	M1	YES	LIKELY	24 homes	Site drainage design challenges
Meadowood	M2	NO	NO	-	Fails 21-day bacteria travel time
	M3	NO	NO	-	Fails 21-day bacteria travel time

Typical house size is 3 bedrooms (450 GPD per home) unless otherwise noted.



# Order of Magnitude Opinion of Costs

With Standard 21-day Bacteria Travel Distance Requirement									
Location		'Real World' Potential	Opinion of Cost (-30 to + 50%)		-		Cost per Home (-30% to +50%)		
Great Hammock Beach	G1	UNLIKELY	\$	1,368,000	10 homes	\$	136,800		
Indiantown	IND1	UNLIKELY	\$	948,000	17 homes	\$	55,765		
Ingham Hill	ING1	VERY LIKELY	\$	1,704,000	33 homes	\$	51,636		
Meadowood	M1	LIKELY	\$	2,004,000	24 homes	\$	83,500		

Note: Average home size of 3 bedrooms (450 GPD per home)

Costs include 20% for Engineering/Permitting/Legal/Administrative

DISCLAIMER: Since Fuss & O'Neill has no control over the cost of labor, materials, equipment or services furnished by others, or over the Contractor(s)' methods of determining prices, or over competitive bidding or market conditions, Fuss & O'Neill's opinion of probable Total Project Costs and Construction Cost are made on the basis of Fuss & O'Neill's experience and qualifications and represent Fuss & O'Neill's best judgment as an experienced and qualified professional engineer, familiar with the construction industry; but Fuss & O'Neill cannot and does not guarantee that proposals, bids or actual Total Project or Construction Costs will not vary from opinions of probable cost prepared by Fuss & O'Neill. If prior to the bidding or negotiating Phase the Owner wishes greater assurance as to Total Project or Construction Costs, the Owner shall employ an independent cost estimator.



# Order of Magnitude Opinion of Costs

With 5 Log pathogen reduction vs 21-day Bacteria Travel Distance Requirement

Location		'Real World' Potential	Opinion of Cost (-30 to + 50%)		Number of Homes	Cost per Home (-30% to +50%)	
Great Hammock Beach	G1	UNLIKELY	\$	1,368,000	10 homes	\$	136,800
Indiantown	IND1	UNLIKELY	\$	948,000	17 homes	\$	55,765
Ingham Hill	ING1	VERY LIKELY	\$	840,000	33 homes	\$	25,455
Meadowood	M1	LIKELY	\$	2,004,000	24 homes	\$	83,500

Note: Average home size of 3 bedrooms (450 GPD per home)

Costs include 20% for Engineering/Permitting/Legal/Administrative

DISCLAIMER: Since Fuss & O'Neill has no control over the cost of labor, materials, equipment or services furnished by others, or over the Contractor(s)' methods of determining prices, or over competitive bidding or market conditions, Fuss & O'Neill's opinion of probable Total Project Costs and Construction Cost are made on the basis of Fuss & O'Neill's experience and qualifications and represent Fuss & O'Neill's best judgment as an experienced and qualified professional engineer, familiar with the construction industry; but Fuss & O'Neill cannot and does not guarantee that proposals, bids or actual Total Project or Construction Costs will not vary from opinions of probable cost prepared by Fuss & O'Neill. If prior to the bidding or negotiating Phase the Owner wishes greater assurance as to Total Project or Construction Costs, the Owner shall employ an independent cost estimator.




#### Now What?

- Desktop Evaluation of Remote Community Locations
  - Great Hammock Beach
  - Indiantown
  - Ingham Hill
  - Meadowood




# Overall Map



FUSS&O'NEILL


## Site 12 – 52 Spencer Plain Road



Note: Site can handle larger flows with 5 log reduction in pathogens through UV



### Gardella Site



#### Evaluated in Spring 2000

Identified as site with second highest disposal capacity per Weston & Sampson Report dated 1993.

Site Characteristics:

37 Acres

Capacity: 150,000 GPD<sup>1</sup>

Evaluated to treat flow from the following Focus Areas:

Chalker Beach

Indiantown

Saybrook Manor


Maple Ave. North to Gardella Site  $\rightarrow$  Approx. 1.7 miles (Conveyance cost approx. \$2.7M)<sup>2</sup>

Saybrook Manor to Gardella Site  $\rightarrow$  Approx. 2.2 miles (Conveyance cost approx. \$3.5M)<sup>2</sup>

#### Notes:

1.) Flow is based on Draft  $A_{\mbox{Municipal}}$  Regulations that were never adopted by DEEP

2.) Conveyance costs estimated assuming \$300 per LF of sewer main.





### Donnelley Site and OS High School





### Site 8 – Ingham Hill Farm/Gravel Pit





#### Next Steps

Complete Conventional Systems/Continue AT Regs **Obtain Access to Sites** Boots on the Ground Dig and log test pits with DEEP Run grain size analysis of soil Determine permeability samples Test phosphorus sorption capacity of soil Install groundwater standpipes Monitor high groundwater levels Compare Costs vs AT with Updated Field Information Petition for 5-Log Pathogen Reduction Submit Revised Plans to DEEP and OSWPCA





# Questions

Kurt A. Mailman, P.E. kmailman@fando.com 860-646-2469 ext. 5244



#### Decentralized Nutrient Removal Systems

Decentralized - Advanced Treatment - "Mini" treatment plants at each home



•

Textile Filter



Aerated Media Filter



Trickling Filter



### Nitrogen and Pathogen Reduction

- Aeration Systems
  Textile Filters
  Peat Filters
  Shallow Narrow Drainfields
  Sand Filters, etc.
- UV disinfection







#### Decentralized Dispersal Systems



Drip Dispersal



Shallow Narrow Drainfield\*



#### **Recirculating Sand Filter**

\* Shallow Narrow Drainfield Figure Courtesy of URI



#### More Decentralized Dispersal Systems



#### Bottomless Sand Filter -Complete



Smaller Bottomless Sand Filter



#### HDPE Leaching Galleries



# Textile Filter











### AT Treatment Train





# Effluent Pump Chamber





# Sequencing Distribution Valves





# Treatment Train - Landscaped





### Treatment Train with Nutrient Removal - NY






### Proprietary Low Profile Leaching System





# Conventional Septic System



#### **Ground Water**





#### Step 4: Construction

Construct System Improvements
Contractor pulls Permit to Construct
WPCA Site Manager oversight
WPCA administers contract
Pay Requisitions

- Change Orders
- Recordkeeping
- Communication with Property Owners
- Ensures work is Clean Water Fund eligible







#### Upgrade Standards - Conventional

#### Leaching System

- Public Health Code Compliant
- Max. 4' new component height
- Max. Depth of System 8 ft
  - No Cesspools
  - Minimum 2/3 of Effective Leaching Area
- 72 sq. ft leaching per bedroom
- Must have 24 inches from the bottom of the leaching system and seasonal high groundwater
- OTHERWISE ADVANCED TREATMENT REQUIRED!



