



Massachusetts Water Resources Authority

High Flow Operation of the Deer Island Treatment Plant

NEWEA
CSO/Wet Weather Issues Conference
10/26/15
Ethan Wenger
Manager, DITP Process Control, MWRA



Agenda

- Overview of MWRA and Collection System
- DITP Treatment Process
- Equipment Critical to High Flow Operation
- Wet Weather Process Operation



-




- 2 Treatment Plants
 - Deer Island
 - Clinton
- 12 Pump Stations
- 4 Headworks
- 5 CSO Facilities

- 2 Treatment Plants
 - CWTP
 - Quabbin
- 10 Pump Stations





MWRA Sewer System



Chelsea Creek Headworks

Peak Flow 350 MGD

Columbus Park Headworks

Peak Flow 182 MGD

Ward Street Headworks

Peak Flow 256 MGD

Nut Island Headworks

Peak Flow 360 MGD



Combined Sewer Overflow Control Program


- Combined Sewer Communities
- Boston
- Cambridge
- Chelsea
- Somerville





Annual CSO Volume Has Been Reduced Dramatically

- 32 of 35 projects have been completed to date
- Annual CSO volumes have already been reduced by 2.7 billion gallons
- Approximately 90% of the remaining CSO flows are treated







Dramatic Improvements In Bacterial Water Quality

**1987-1998 (Before Secondary Treatment
and South System transfer)**

**1999 - 2010 (After Secondary Treatment
and New Outfall)**



Average *Enterococcus* counts in Boston Harbor in wet weather

The lighter the blue, the better



Deer Island Treatment Plant

Overview of Deer Island Treatment Process





Deer Island Project History





Deer Island Project History






Deer Island Treatment Plant

- \$3.8 Billion to Build
- Treatment Capacity:
 - Maximum
 - 1.3 Billion Gal/Day
 - Up to 700 MGD by Secondary Treatment
 - Average Daily Flow:
 - 350 MGD






Deer Island Process Flow Diagram





Primary Stacked Clarifiers



Primary Treatment Has 48 Stacked Clarifiers

72 Primary Sludge Pumps

14 Primary Scum Pumps

Each Clarifier:

1.4 Million Gallons (15,252 sq ft)

Five Chain Collector Mechanisms

Process Requires 42 Out Of 48 Always Available

Challenges:

Covered & Stacked

Most work requires confined space entry



Secondary Process



Biological Treatment - Activated Sludge (Pure O₂)

Over 900,000 Square Feet Facilities (1/3 Covered)

Pure Oxygen Generation Facility

Odor Control - Carbon Adsorption



Secondary Clarifiers



**Secondary Treatment Has
54 Stacked Clarifiers**

Each Clarifier:

1.36 Mgal, 14,350 sqft

Six Collectors

22 Field Instruments

**70HP 3000GPM Return
Sludge Pump**

**Process Requires
50 Out of 54 Always
Available**

Challenges:

Stacked

Confined Space Entry



Anaerobic Digestion

12 - 3 MGal Digesters Heated to 98 deg F
8 digesters operated at any given time





Wet Weather Process Control

- Put on more primary clarifiers
- Put on more pumps
- Adjust Secondary Process (wasting rate)
- Put on backup power (severe storms)
- Pay extra attention to chlorine dosing



NPDES Permit Parameters

Parameter	Permit Limit	Typical Values
Total Suspended Solids	45 mg/L (weekly) 30 mg/L (monthly)	10 mg/L
Carbonaceous Biochemical Oxygen Demand	40 mg/L (weekly) 25 mg/L (monthly)	6 mg/L
pH	6-9 S.U.	6.5 S.U.
Total chlorine Residual	<0.63 mg/L (daily) <0.45 mg/L (monthly)	<0.04 mg/L <0.04 mg/L
Fecal Coliform	<14,000/100 mL	<5/100 mL



Wet Weather Infrastructure

- North Main Pump Station
- South System Pump Station
- Flow Control Gate
- Outfall Tunnel



Massachusetts Water Resources Authority

North Main Pump Station



**Maximum
Capacity -
788 MGD**



**A Former DITP Facility - Upgraded With New Pumps & Motors
Complex Construction Due To Continuous Operation**



North Main Pumps

- Manufactured by Fairbanks-Morse
- Centrifugal Pumps
- Capacity of 110 MGD
- Total head of 150 ft
- 3500 HP Motor
- 10 pumps installed



South System Pump Station

**New Pump Station With Dry/Wet Well Design
Serving Separated System Must Be 100% Reliable**





South System Pumps


- Manufactured by Worthington
- Vertical, Non-clog Centrifugal Pumps
- Capacity of 65 MGD
- Total Head of 90 ft
- 1250 HP Motor
- 8 Pumps Installed in 1995, online in 1998.



Flow Control Gate

Delivers Primary
Effluent to
Disinfection


Gate Fully
Lowered





Secondary/Disinfection Layout


Primary
Effluent
Channel



Flow Control Gates




Sea Gull's Eye View






Deer Island Construction – Tunnels

The Boston Harbor Project's Major Tunnels





Deer Island Construction – Outfall Tunnel Diffusers





Summary

- Wet Weather Operation at DITP is challenging but effective
- No NPDES permit violations for 8 years
- Continuing improvement in reducing CSO activations
- Dedicated Team of Wastewater Professionals is Key to Success



Secondary Clarifier Weirs at Max Flow condition





Acknowledgements

- Mike Hughes, Senior Shift Manager
- David Duest, Director, DITP
- John Colbert, Deputy Director, DITP
- Lisa Wong, Program Manager, Process Monitoring
- Charlie Tyler, Program Manager, Process Engineering
- Brian Kubaska, Manager, Process Control and SCADA
- DITP Operations
- DITP Process Control
- DITP Technical Information Center



Thank you!

Questions?

Contact: Ethan Wenger
Title: Manager, Process Control
E-mail: ethan.wenger@mwra.com
Phone: 617-660-7689