


Prove It! Demonstrating Performance of a Combined Carbon and Ammonia Removal BAF

Erik N. Meserve², Terry L. Desmarais¹,
Paula Anania¹, Jon R. Pearson²,
Erik J. Grotton³

¹City of Portsmouth, NH | ²AECOM | ³Blueleaf Technologies



January 26, 2016



AECOM

Presentation Outline

- Introduction & Background
- Demonstration Study Drivers & Goals
- Methodology and Equipment
- Experimental Approach & Results
- Conclusions
- Questions



Introduction



– Project location - Portsmouth, NH


- Population 21,200
- Historic seaport / summer tourist destination

– Two WWTFs (Peirce Island and Pease)

- Combined sewer system

– Peirce Island WWTF Design Flows

- Average day flow 4.5 mgd
- Peak flow 22 mgd



Background



- Peirce Island WWTF originally built in 1964 – primary treatment with disinfection
- 1985 – NPDES permit issued with 301(h) waiver
- Upgraded in 1990 to advanced primary with filtration
- Upgraded in 2002 as chemically enhanced primary treatment
- 2005 draft permit issued with 301(h) waiver – denied
- 2007 new permit issued with secondary requirements

WWTF Upgrade Process Selection



- Provide secondary treatment within existing WWTF fence line
- Desk top evaluation of 8 high rate treatment technologies
 - ✓ Based on capital cost, 20 year life cycle cost, and cost to value ratios using a weighted value matrix
- Top three technologies piloted in the field in 2012:
 - Activated Sludge with BioMag
 - MBBR with DAF
 - Biological Aerated Filter (BAF)
- BAF selected based on cost and non-monetary criteria matrix as the technology that best met the City's needs

Demonstration Study Drivers & Goals



- Near the end of 2012 Initial Piloting, EPA informed City that nitrogen removal now required
- 2012 Initial Piloting provided limited data on BAF combined stage carbon oxidation and ammonia removal (CN) and performance at cold temperatures
- Limited installations of combined stage CN BAF in the US & proposed loading rates at high end of range of operating installations
- Need for additional data on BAF backwash solids coagulation, settling, thickening, and dewaterability
- Desire for City's WWTF operations staff to gain experience with BAF process

Demonstration Pilot Study Methodology



- Operate pilot scale first stage BAF to remove BOD and oxidize ammonia at or near proposed full-scale maximum month loading rate at cold temperatures
- Conduct jar tests on BAF backwash to establish effective ferric chloride and polymer doses for coagulation
- Conduct settling tests of combined raw wastewater and BAF backwash to assess settling performance
- Conduct thickening compression tests of combined primary sludge and BAF backwash to assess thickening performance
- Conduct bench scale testing of dewaterability of thickened combined primary sludge and BAF backwash




Demonstration Pilot Study Equipment

- Pilot scale primary clarifier
- Sized to mimic hydraulic overflow rate of full scale primary clarifier
- Raw wastewater pumped to influent
- Primary effluent pumped to BAF Pilot



Demonstration Pilot Study Equipment



Demonstration Pilot Study Equipment



Demonstration Pilot Study Equipment



Experimental Approach and Results



Frozen Feed Pump



Snapped Backwash Pipe

BAF Pilot

- Idle Stage 1 pilot unit re-started January 2, 2014
- Extremely cold temperatures presented operating challenges
- Unusually cold wastewater temperatures coupled with above ground piping and exposed metal pilot column inhibited nitrifier growth until mid-April
- Temperature correction applied to design loading rates to compensate for rising wastewater temperatures April-June
- BAF effluent analyzed for COD, BOD₅, TSS, TKN, NH₃, NO₂, NO₃, PO₄, alkalinity, temperature

Experimental Approach and Results


BAF Pilot

- Operated January – June 2014
- Target Loading Rates:

Parameter	Loading Rate Objective
Hydraulic Loading Rate	1.04 gpm/sf
BOD ₅ Loading Rate	147 lb BOD ₅ per 1,000 ft ³ /d at 10°C 165 lb BOD ₅ per 1,000 ft ³ /d Corrected
NH ₃ -N Loading Rate	13.7 lb NH ₃ -N per 1,000 ft ³ /d at 10°C 15.3 lb NH ₃ -N per 1,000 ft ³ /d Corrected


Experimental Approach and Results

BAF Pilot – Influent & Effluent BOD₅




Experimental Approach and Results

BAF Pilot-Influent & Effluent TSS




Experimental Approach and Results

BAF Pilot-Influent & Effluent $\text{NH}_3\text{-N}$




Experimental Approach and Results

BAF Pilot- BOD₅ Loading Rate Versus Removal




Experimental Approach and Results

BAF Pilot- NH₃-N Loading Rate Versus Removal




Experimental Approach and Results

Coagulation Jar Tests




Experimental Approach and Results

Coagulation Jar Tests – Overlaid Contour Plot




Experimental Approach and Results

Settling Tests




Experimental Approach and Results

Settling Tests




Experimental Approach and Results

Combined Primary Sludge & BAF Backwash Compression Tests



Experimental Approach and Results


– Combined Primary Sludge & BAF Backwash Compression Tests



Experimental Approach and Results

Thickened Primary Sludge & BAF Backwash Dewatering Tests

- Thickened sludge from Compression Tests tested by screw press vendors



- Test results:

Parameter	FKC	Huber
Predicted polymer usage	22 lb/dry ton	25 – 35 lb/dry ton
Predicted dewatered cake solids	27.65%	>27%

Conclusions

- ✓ BAF Demonstration piloting confirmed design loading rates for BOD₅ of 147 lb/1000 ft³/d and up to 13.7 lb/1000 ft³/d for NH₃-N
- ✓ Backwash coagulation: FeCl₃ dose of 20 mg/l and polymer dose > 0 provide effective coagulation
- ✓ Settling column tests confirmed satisfactory co-settling of raw wastewater and BAF backwash
- ✓ Combined sludge compression tests confirmed primary sludge and BAF backwash can be effectively co-thickened
- ✓ Bench-scale testing confirmed that co-settled, co-thickened primary sludge and BAF backwash can achieve 27% dewatered solids with reasonable polymer dosage

Thank You

erik.meserve@aecom.com



For More Information, Project Documents Available at:
www.portsmouthwastewater.com/resources

AECOM