

City of Nashua, New Hampshire

WWTF Headworks Upgrade



Presenters:
Noelle Osborne – Nashua WWTF
Andy Morrill – Wright-Pierce



NEWEA Annual Conference
Session 18
January 24, 2017

Presentation Overview

- ✓ Nashua WWTF Background
- ✓ Project Drivers
- ✓ Equipment Selections
- ✓ Operational Solutions
- ✓ Additional Improvements
- ✓ Project Overview/Status
- ✓ Q & A




Nashua WWTF Background

- Population
 - 87,000
- Collection system
 - over 400 miles
 - combined
- Main WWTF
 - average daily flow 12 MGD
 - peak hourly flow 50 MGD
- Wet weather facility
 - peak hourly flow 60 MGD



Nashua WWTF Background

- Collection System
 - Total - 420 miles
 - Combined - 100 miles
 - Separate Sanitary - 190 miles
 - Separate Storm - 130 miles
 - 13 Pump Stations
 - CSO Structures
 - Nashua River - 4
 - Merrimack River - 5
- Service Area
 - Nashua, NH
 - Hudson, NH
 - Merrimack, NH
 - Tyngsboro, MA



Nashua WWTF Background

Nashua WWTF - 1965



Nashua WWTF Background

Nashua WWTF - 2002



Nashua WWTF Background

Construction Projects

1959
original
primary
plant

1972
collection
system &
plant exp.

1985
secondary
treatment
upgrade

1998
anaerobic
digester
complex

1999
headworks
renovation

2006
wet
weather
facility

2014
dewatering
and grit
upgrade

Influent
screening and
pumping in
current
configuration


Upgrades to
grit removal
portion of
headworks

Current
screening
facilities

Nashua WWTF Background

- Existing Screening Equipment
 - Two IDI Climber Screens
 - ◆ ¾-inch bar spacing
 - ◆ lift to second level – EL. 19.5
 - ◆ submerged operation - hydraulic drive
 - Two Lakeside Wash Presses
 - ◆ two-stage
 - Screw Conveyors
 - ◆ combined hopper to vertical screw

EL. 19.5



Project Drivers

- Screening Equipment
 - Reached end of **“Useful Life”**
 - one screen offline prior to design
 - channel track repair
 - one screen offline during design
 - arm assembly replacement
 - one screen currently used during **“emergencies only”**
 - washpress frequently offline
 - bearing replacement



Project Drivers

- Screenings Handling
 - vertical screw conveyor abandoned
 - discharge to small carts
 - carts hoisted to ground level
 - labor and time intensive
 - safety concerns



Project Drivers

- Downstream Ragging
 - Grit Removal System
 - jammed shaftless screw conveyor
 - increased cleaning & maintenance
 - Digester Complex
 - decreased operational efficiency
 - added cost to remove matted rags



Project Drivers

- Influent Flooding
 - Screen Room
 - high level of operator attention
 - additional cleaning & maintenance
 - collapsed HVAC ductwork



Equipment Selections

➤ KEY GOALS

- increase mechanical reliability
- increase screenings capture
- effective screenings washing
 - reduce quantity & disposal costs
- **automated** screenings conveying to ground level
- upgrade ventilation and odor control as necessary
- accomplish goals within available funding



Equipment Selections

➤ Type of Screen

➤ Climber

- heavy duty provided rake-arm motor/drive above channel
- requires substantial headroom space
- limited screenings removal capacity
 - once per cycle




Equipment Selections

➤ Type of Screen


➤ Chain & Flight (Multi Rake)

- front-raked & return
- heavy-duty application
- highest screenings removal
- requires minimal headroom
- least impact on hydraulic capacity with smaller bar spacing



Equipment Selections

Estimated Additional Screenings Generation for Nashua, NH Headworks



Note: Based on Typical generation rates depicted in previous graph.

Equipment Selections



Layout Alternatives

- Alternative 1 – Screens discharging at ground floor level (Elevation 36.0)
- Alternative 2 - Screens discharging to new mezzanine (Elevation 25.0)
- Alternative 3 - Screens discharging to screening room (Elevation 19.5)



Equipment Selections


Alternative 1 – Screens Discharge at EL. 36.0



Equipment Selections



Alternative 1 – Screens Discharge at EL. 36.0

- Screens discharge to wash presses at EL. 36.0
 - must use chain and flight screens
- Wash presses discharge directly to screenings container
- Workable ground floor impacts
- Highest cost but within budget
- Best long-term solution



Equipment Selections


Alternative 2 – Screens Discharge at EL. 25.0



Equipment Selections



Alternative 2 – Screens Discharge at EL. 25.0

- Screens discharge to wash presses at EL. 25.0
 - must use chain and flight screens
- Wash presses discharge to 30-degree incline screw
- No ground floor impacts
- Moderate cost within budget



Equipment Selections


Alternative 3 – Screens Discharge at EL. 19.5



Equipment Selections

Alternative 3 – Screens Discharge at EL. 19.5


- Screens discharge to wash presses at EL. 19.5
 - chain and flight screens or climber
- Wash presses discharge to 45-degree incline screw
- Second horizontal screw
- No ground floor impacts
- Lowest capital cost within budget



Equipment Selections


Alternative 1 – Screens Discharge at EL. 36.0

- Huber Rake-Max Screens
 - 3/8" bar spacing
- Vulcan Wash Presses




Equipment Selections

Alternative 1 – Screens Discharge at EL. 36.0



Equipment Selections



Alternative 1 – Screens Discharge at EL. 36.0

Equipment Selections



Alternative 1 – Screens Discharge at EL. 36.0

Operational Solutions


➤ Hydraulic Modeling

➤ existing conditions

➤ flow to WWTF

➤ theoretical

➤ actual



➤ proposed conditions

➤ one & two screen operation

➤ each screen - 60 MGD

Operational Solutions

- SOP Review/Operator Input
 - influent gate
 - wet well levels
 - raw sewage pumps
 - secondary bypass



Operational Solutions

- Automation of
 - third raw sewage pump & influent gate
 - third raw sewage pump
 - control via wet well level
 - influent gate control
 - **“storm event” virtual button**
 - gate to ready position
 - adjust influent gate to maintain
 - » wet well level - 8.0 feet
 - » influent flow - 50 MGD




Operational Solutions

- Automation of
 - secondary bypass gate operation
 - after third raw sewage pump started (~32 MGD)
 - **AND** wet well level 7.5-feet (rising)

Storm Event Duration (hours)	Bypass Flow (MGD)	Secondary Flow (MGD)
≤ 6	18	32
6 to 12	24	26
≥ 12	32	18

Additional Improvements


- Restore Existing Venturi Flow Meters
 - secondary effluent (60-inch)
 - secondary bypass (36-inch)



Additional Improvements


➤ Replace HVAC

- wet well
- dry well
- ductwork



Additional Improvements

- Replace
 - Aged MCCs
 - MCC-CB4
 - MCC-2
 - Wet Well Odor Control
 - fiberglass fan
 - new GAC
 - new bypass
 - new mist eliminator



Project Overview/Status

Construction Cost: \$2.85M

Engineering Cost: \$0.65M

Total Cost: \$3.50M

Currently 20% through Construction Budget

Substantial Completion: May 23, 2017

Final Completion: August 21, 2017

Currently 51% through Contract Time

Questions

