





- The Problem
- The Design
- Construction
- Lessons Learned
- Project Status






#### **Sanitary Sewer Overflows**

- Occur during Wet Weather
- Urban Flooding
- Requires Storm Response
- Public Health Risk
- Environmental Hazard
- Quality of Life Issue








#### The Goal

- Mitigate SSOs
- Minimize Cost
- Minimize Disruption
- Utilize CSO Storage Tunnel








# The Problem CSO Storage Tunnel


## **Dry Weather Operation**





# The Problem CSO Storage Tunnel


### **Wet Weather Operation**





# The Problem CSO Storage Tunnel

#### **Tunnel is Full!**






#### The Problem


#### **Globe Street Sewer Plans**

- Early 1900s
- 66" Brick Sewer
- "Four Corners"
   Intersection





#### The Problem









### The Design Challenges

#### **INSTALL A BIGGER PIPE!**



#### **Critical Sewer Main**

Maintain wet weather flows

#### **Congested Utilities**


- Use existing sewer corridor
- No bypass pumping
- Sewer live during construction

#### **Traffic & Neighborhood Issues**


- Minimize disruption
- Maximize traffic flow







### The Design




### **Construction Sequence**

- 1. Excavate Existing Sewer
- 2. Pour Concrete Base
- 3. Cut Top Off Sewer
- 4. Maintain Sewer Flows
- 5. Install 4' x 6' Culvert
- 6. Build Brick Invert Shelf



### The Design



#### Watertight

- Hydrophilic Water Stop
- Butyl Rubber Seal/STS Gasket
- External Joint Wrap

#### **Corrosion Prevention**

Anti Corrosion Admixture

### **Integrity of Brick Sewer**

Bid Allowance for Repairs















## **Construction**First Concrete Pour









## **Construction**Removing Brick Sewer





## **Construction**Removing Brick Sewer





## **Construction**First Section





### Construction





# **Construction**Building Brick Invert





# **Construction**Sealing Joints





### Construction





# **Construction**When it rains...







## **Construction**Demolishing Manhole





## **Construction**Installing New Manhole





## Construction Rock





## Construction Drill rig & Pneumatic hammer





# **Construction**Pre-drill Rock







### **Construction**Cast-in-place Closure Pour












## **Construction**Sewer Junction












**Engineering a Better Environment** 

## **Construction**Utility Conflict

#### **Utility Conflict**

- Gas
- Telephone
- Electric
- Telephone










# **Construction**Utility Conflict









## **Construction**Closure Pour









#### Construction



### **Transition Manhole Excavated**

- 33" Sewer in front
- 66" Sewer in back



#### Construction



Wet-weather event
Flows contained in trench





## **Construction**Last Manhole!





## **Construction**Last Manhole!





#### Construction

























#### **Project Team**



**CITY OF FALL RIVER** 

Owner



**WRIGHT-PIERCE** 

Engineer



**KEVILLE ENTERPRISES** 


**RPR** 



**KR REZENDES** 

Contractor







**Project Closeout** 

**✓** Operational for 7 Months

✓ No Dancing Manholes

✓ Planned CSO Tunnel Operational Adjustments are a Success







