Tighe&Bond Engineers | Environmental Specialists



RESPONDING TO WINTER STORM RILEY: THE CITY OF QUINCY'S EMERGENCY RECONSTRUCTION EFFORTS

NEWEA CSO Wet Weather Issues Conference October 30, 2018

Paul Costello, PE – City Engineer Marina Fernandes, PE – Project Manager David Murphy – Principal In Charge

PRESENTATION OVERVIEW

- 2018 Storm Riley
- Post Storm Emergency Assessment
- FEMA Reporting Development
- Environmental Notifications/Certifications
- Construction Phase Services



CITY OF QUINCY





- Boston's immediate southern suburb.
- 8th largest city in the state.
- Known as the "City of Presidents," :
 - birthplace of 2 U.S. presidents: John Adams and John Quincy Adams;
 - birthplace of John Hancock, a President of the Continental Congress and the first signer of the Declaration of Independence.




2018 STORM RILEY

Another Round of Moderate to Major Coastal Flooding Tonight


Nantucket:

Forecast 7.7 feet* (Major)



Boston:

Forecast **14.9** feet* (Moderate – Major)



Latest surge just over 3 feet at Nantucket and Boston

* MLLW



Published: Friday, March 02, 2018 9:12 PM Website: www.weather.gov/boston

Twitter: @NWSBoston Facebook: http://www.facebook.com/NWSBoston





2018 STORM RILEY










POST STORM EMERGENCY ASSESSMENT – MOBILIZATION






POST STORM EMERGENCY ASSESSMENT – GIS TOOL APPLICATION


 GIS Application for Efficient Field Data Collection

- Application created for the City using ESRI Collector for ArcGIS
 - Photographs
 - GIS Points
 - Measurements
 - Notes



Tighe&Bond

EMERGENCY REPAIR AREAS



PROJECT COSTS PHASE 1

- Total Engineering Fee: \$200,000
- Total Construction Costs: \$1.2M
 - Voted on 03/12
 - Total vote included additional \$1.7M for roadways and tide gates.

ORIGINAL PROJECT SCOPE

TOTAL ENGINEERING FEE - ORIGINAL SCOPE \$ 200,000

			TOTAL CO	NSTRUCTION BUDGE	T - ORIGINAL SCOPE	\$ 1,200,000
Location	Location Name	Work Item	Work Classifications	Status	Contractor	Budgeted Const. Cost - COMPLETED
Location 1	E. Squantum near Nickerson Park	1.1	Erosion Repair	Completed	MAS	\$ 30,000
		1.2	Revetment restoration			
		1.3	Outfall repair			
		1.4	Repair to public access			
Location 2	Squantum- Bayside Road	2.1	Erosion Repair	Completed Original Scope + Added Scope before April 2	MAS	
		2.2	Exposed sewer pipe			\$ 120,000
		2.3	Revetment Repair			7 120,000
		2.4	Debris clearing			
	Adam's Shore – Shore Ave/ Chickatabot Road/ Norton Road	3.1	Revetment Repair (Grout Injection)	Completed	AA Will	
Location 3		3.2	Repair to public access			\$ 13,000
	Adam's Shore – Terne Road/Shellton Road	4.1	Seawall block repair		AA Will	
		4.2	Revetment Reconstruction	Completed		
		4.3	Revetment Repair (Grout Injection)			
Location 4		4.4	Levelling Course			\$ 150,000
		4.5				
		4.5	Slope Protection Above Seawalls / Slope Repair			
			Seawall Replacement			
	Hough's Neck – Post Island Road	5.1	Seawall block repair	Completed	AA Will	
Location 5		5.2	Revetment Repair (Grout Injection)			
		5.3	Levelling Course			\$ 150,000
		5.4	Slope Protection Above Seawalls / Slope Repair			,
		5.5	Repair to public access			
		5.6	Seawall Replacement			
	Hough's Neck – Sea Street & Babcock Street	6.1	Seawall block repair	Completed	Cashman	
Location 6		6.2	Revetment Repair (Grout Injection)			\$ 135,000
		6.3	Levelling Course			\$ 135,000
		6.4	Slope Protection Above Seawalls			
Location 7	Evacuation Boardwalk	7.1	Boardwalk Repairs near 700 Sea Street	Completed	Cashman	\$ 40,000
Location 8	Hough's Neck – Manet Ave/Nut Island Ave	8.1	Seawall Repair	Completed	Cashman	,
		8.2	Levelling Course			\$ 309,200
		8.3	Erosion Repair			
Location 10	Hough's Neck – Edgewater Drive	10.1	Seawall repair-Grout	Completed	MAS	
		10.2	Erosion Repair			
		10.3	Revetment Repair/reconstruction			\$ 100,000
		10.4	Revetment repair- Grout injection			
		10.5	Repair to public access			
Location 11	Quincy Point – Wharf Site	11.1	Debris clearing	Mayors office requested no	-	
	behind CVS Quincy Health Center/Bus	11.2	Cutting of piles 3 (three) feet below mudline.	action		
Location 12	Barn Rd**	12.1	Pavement restoration	Completed	AA Will	\$ 101,773
Location 15	Squantum Seawall**	15.1	Revetment Repair within MHWL	Completed	AA Will	\$ 35,906
New Location	Bayswater Outfall	New Work	Cashman's purchased materials and spent time attempting to repair outfall before end of April 2 deadline	Not completed	Cashman	\$ 15,800

MAS CONSTRUCTION TOTAL \$ 250,000

AA WILL CONSTRUCTION TOTAL \$

CASHMAN CONSTRUCTION TOTAL \$

450,679

LOCATION 1 – EAST SQUANTUM





Roadside view of grouted joints along Dorchester Ave.



Revetment repair and curb reset at Nickerson Beach.




LOCATION 2 – BAYSIDE ROAD





Revetment repair along Bayside Road.

DESIGN DETAILS



LOCATION 4 – TERNE RD. / SHELTON RD.







LOCATION 8 – MANET AVENUE









Department of Environmental Protection

One Winter Street Boston, MA 02108 • 617-292-5500

Charles D. Baker Governor Matthew A. Beaton Secretary

Karyn E. Polito Lieutenant Governor Martin Suuberg Commissioner

To: Coastal Conservation Commissions

Date: March 30, 2018

Subject: Emergency Declaration Extension until May 2, 2018

EMERGENCY DECLARATION EXTENDED UNTIL MAY 2ND

Extension issued on Friday March 30th

PROJECT COSTS PHASE 2

- Additional
 Total
 Engineering
 Fee: \$55,000
- Total Construction Costs: \$500k
 - Voted on 04/23

RECOMMENDED ADDITIONAL PROJECTS										
Location	Location Name	Recommended by	Notes	Status	Budgeted Const. Cost					
Location 1	East Squantum	T&B	Complete remaining grouting on East Squantum	Not Completed. Assigned	\$ 20,000					
Location 8	Manet Road @ Oswego Street	T&B	Manet seawall cap repair	Assigned. Site Visit 4/11	\$ 50,000					
Location 10	Hough's Neck – Edgewater Drive	T&B	Extended Scope of Grouting	Not completed. Not Assigned	\$ 20,000					
Location 2	Squantum- Bayside Road	T&B	Repair includes protecting sewer pipe and remaining slope stabilization	Assigned. Site Visit 4/11	\$ 150,000					
Location 14	Broadmeadows Middle School	City	Broadmeadows pipe repair and inline one way valves	Not Completed	\$ 15,000					
New Location	Norton Beach Outfall	City	Install seeping structure and 18" pipe in place	Not Completed. Assigned	\$ 45,000					
New Location	Bayswater Outfall	T&B	Total cost does not include pipe, staples and Cashman's time: grand total \$15.8k	Not completed. Assigned	\$ 80,000					
New Location	Rockland Street	T&B	Rockland Street outfall repair.	Not Completed	\$ 25,000					
New Location	Chickataubout Road	W&C	Chickataubout Tide Gate (TG#15) system replacement, budget \$10,000 via OnCall WSE Contract	Not Completed	\$ 10,000					
New Location	Edgewater Drive	W&C	Edgewater Tide Gate (TG#18) replacement of slide gate and guides via OnCall WSE Contract	Not Completed	\$ 35,000					
New Location	Rockland Street	W&C	Rockland St Gate (TG#26) replacement of broken flapper gate with a tide flex valve via OnCall WSE Contract	Not Completed	\$ 5,000					
New Location	Various Locations	T&B	Outfall repairs stemming from the outfall emergency assessment. Assessment ongoing.	Not Completed	\$ 25,000					
All Locations	Police Details	City	Located as necessary	Not Completed	\$ 20,000					


RECOMMENDED ADDITIONAL FUNDING \$ 500,000




NORTON BEACH OUTFALL







BAYSWATER OUTFALL







ROCKLAND STREET OUTFALL





PLANNING FOR THE FUTURE

- Finishing the Design of Adam Shore Seawall Project – 8,000 linear feet of new seawall;
- Ongoing Design of Manet Seawall Project;
- Completing the Hazard Mitigation Plan for the City;
- Pro-active maintenance of outfall structures and tide gates prior to every storm;
- Communication with residents about evacuation routes and safety procedures.

QUESTIONS

