



2020 ANNUAL
CONFERENCE & EXHIBIT



January 29, 2020

SESSION 26

CSO/WET WEATHER 2:

PROJECTS BIG AND BIGGER IN CSO

HARTFORD METROPOLITAN DISTRICT WET WEATHER EXPANSION PROJECT PHASE 2 – NEW 200 MGD WET WEATHER TREATMENT FACILITIES

PRESENTERS – Jeff Bowers, MDC and Brian McGuire, Arcadis





Presentation Agenda

- 1 The Metropolitan District Overview
- 2 Project Drivers and Goals
- 3 Wet Weather Treatment Facilities In-Depth
- 4 SCADA Implementation
- 5 Other Project Elements
- 6 Questions





MDC Overview

- Established in 1929, first on CT River to provide sewage treatment
- Serve 8 Member Towns
 - Responsible for serving 400,000+ customers
- Full-service utility
 - Water Supply, Water Treatment, Distribution Collection, Wastewater Treatment, All support services
- All WPC facilities operate continuously, 24hrs/day, 365 days/year





Project Driver – Clean Water Project

5 Components to the Solution:

1. Eliminate All Sanitary Sewer Overflows (SSOs)
 - Expansion of the HWPCF Treatment Plant
 - Reduction of Combined Sewer Overflow (CSO) and Infiltration (I/I)
2. Reduction of total nitrogen discharge from the wastewater treatment facilities
3. Construction of the South Hartford Conveyance & Storage Tunnel
4. Consolidation of Interceptor Pipes

The screenshot shows the website for the Clean Water Project, specifically the South Hartford Conveyance & Storage Tunnel. The page features a navigation bar with links for 'About The Project', 'Projects', 'Stay Informed', and 'News and Events'. The main content area includes a large image of the tunnel structure, a cross-section diagram of the ground layers (Sand, Varved Clay, Till), and a list of project partners: Clean Water Project, MDC, US EPA, US Army Corps of Engineers, KENNY, CDM Smith, AECOM, BLACK & VEATCH, JACOBS, and PARSONS. Below the main image are two smaller images: 'Wet Weather Expansion' showing a group of people at a construction site, and 'About the Project' showing a view of the city and water. A 'News & Events' section on the right lists two articles: 'Design Develop Construct Journal article: Cleaning Up Connecticut' and 'WNPR story on the MDC's Tunnel Project'. A 'Learn more' button is also present.




Hartford WPCF Overview



Wastewater Treatment Facilities
Heat Recovery

PHASE 1

PHASE 2





Phase 1 - Headworks Facility Expansion


- Bar Rack Facility
- Influent Pump Station
- Fine Screens and Screening Handling
- Grit Removal
- Odor Control





Goals Phase 2 - Wet Weather Treatment Facilities


- Gravity conveyance from Primary Treatment to Secondary and Wet Weather treatment Systems
- Treatment Facilities with capacity to handle 200 MGD
- Expanded and Innovative “Dual Use” Primary Treatment System
- Maximizing flow to Secondary Treatment during Wet Weather Events
- Expansion of discharge capabilities
 - Maximize gravity flow






Phase 2 - Contract 2012-21

- 200 MGD Primary Treatment Capacity
- 110 MGD Wet Weather Treatment Capacity
- 200 MGD Combined Plant Effluent / Wet Weather Flow Pumping and Gravity Discharge Capability





Process Flow Stream





Dual Use Primary Clarifiers

Dual use refers to the ability for the clarifiers to operate under different modes

- Mode 1 – Dry Weather
- Mode 2 – Wet Weather
- Mode 3 - Chemical Enhanced Primary Treatment (CEPT)
- 8 Primary Rectangular Clarifiers
 - Total Area: 75,000sq ft
 - SOR of 1,200 gpd/sq ft at 90 MGD



Dual Use Primary Clarifiers

Dry Weather Mode

Wet Weather Mode

Dual Use Mode


- Addition of Coagulant (ferric or alum) to influent
 - 1 – 2 minute contact time
 - Dose of 20 – 50 mg / L
- Addition of Flocculant (polymer) to forebay
 - Dose of 0.5 – 1.5 mg/L





Dual Use Primary Clarifiers

- 3 Channel Mixing Blowers (2,500 scfm/blower)
- 2 Chemical Feed Blowers (120 scfm/blower)



Dual Use Primary Clarifiers

- 12 Rotary Lobe Pumps (570 gpm/pump)
- 12 Sludge Grinder
- 2 Clarifier Drain Pumps (1600 gpm/pump)
- 6 Gallery Sump Pumps





Dual Use Primary Clarifiers

FRP Effluent Troughs

Primary Scum

- 16 Motorized Dipping Weirs
- 4 Submersible Chopper Pumps (600 gpm/pump)





Chemical Storage Facility




- FRP Storage Tanks
 - 3 Coagulant 12,000 gal each
 - 2 Polymer 2,000 gal each
- 3 Coagulant Feed Pumps
- 2 Polymer Blending Units
- 1 Polymer Transfer Pump
- 4 Chemical Sump Pumps
- Air compressor



Flow Control Gate and Parshall Flumes

- 4 motor operated slide gates
- 4 Parshall Flumes
- 2 Discharge paths based on season
 - Disinfection through WWDT Influent Gate
 - Bypass through WWDT Bypass Gate



Wet Weather Disinfection Tank Hypochlorite Storage and Feed

- 2 FRP Storage Tanks
 - 7,000 gal each
- 3 Metering Pumps
- 1 Transfer Pump
- 2 sample pumps
- 2 sump pumps
- 2 Cl Analyzers
- Air compressor
- 4 Mixers





Wet Weather Disinfection Tank

- Seasonal Operation
- 110 mgd (4.82 m³/s) capacity
- Four passes - 16' W x 165' L (six passes for future flow)
- 10-minute chlorine contact time, 10 mg/L design dosing rate, 5 mg/L dosing rate during CEPT operation of DUPC
- 2 sample pumps and Chlorine analyzers
- 4 Passes
 - 16' wide & 173' long
- 4 Flushing Gates
- Dewatering Pumps
 - 2 - 4,300 gpm/pump
 - 1 - 100 gpm/pump





Combined Effluent Pump Station

- Design Flow
 - Current 200 mgd (8.76 m³/s)
- Design River Level: Elevation 0-32 feet (500-year Flood)
- 6 pumps: 5 Duty, 1 Standby – 40 mgd (1.75 m³/s) each





Combined Effluent Pump Station

- Wet Weather Gravity Flow
- Combined Final Effluent and Wet Weather Flow
- Physical Modeling
 - Flow distribution to pump suctions
 - Flow patterns, free and subsurface vortex formation and swirl
 - Assure satisfactory performance, based on the Hydraulic Institute Standards, ANSI/HI 9.8-1998 (HIS) acceptance criteria.



CEPS WW Inlet Gate (7040)

Wet Weather Bypass Influent

CEPS Final Inlet Gates (7020)

Junctio


Prevents backflow





SCADA Implementation

- Operator/Maintenance Personnel Workshops
- Control Strategy Development
 - Master Wet Weather
 - High Rate Disinfection
 - CEPT Strategies
 - Effluent Discharge
- Desktop Simulation/Demonstration
- Facility “off-line” testing
- Facility “on-line” testing





Other Project Elements – eOM & CMMS

- System O&M Manuals
- Normal/Routine Procedures (SOPs)
- Process Design Criteria
- Operator Log Entries
- Troubleshooting
- Training Documents
- Record Drawings
- Equipment Lists
- Control Descriptions

Tablet & Phone Accessible





Acknowledgements





Questions?

Contact Information



Brian McGuire
Project Civil Engineer
Arcadis
Middletown, CT
Brian.McGuire@arcadis.com
860-503-1451



Jeff Bowers
Plant Manager
MDC
Hartford, CT
J.Bowers@themdc.com
860-278-7850 x3548

