Collection Systems 2: Digging on the Dock of the Bay

Route 28 East Sewer Expansion Project in Barnstable, MA – The Cornerstone of the Future for a Cape Cod Community





2023 Annual Conference – Marriott Copley Place, Boston, MA January 24, 2023



Introduction

- Project Team
- Project Background
- Design Challenges
- Construction





Project Team

- Town of Barnstable, DPW
- Weston & Sampson Engineers, Inc.
- Department of Environmental Protection (DEP)
- Department of Transportation (DOT)





Project Background





Project Background

- 2007 Final Wastewater
 Facilities Plan and Final EIR
- January 2020 CWMP
 - o 3 Phases (30 years)
 - Nitrogen Removal in Coastal Embayments
 - Protection for Drinking Water Wells, Ponds, and Lakes
 - Enhance Economic Development
- Water Resources Advisory
 Committee & DPW Staff



Project Background

- Approx. 11,000 feet of Gravity Sewer
- Approx. 12,000 feet of Force Main Route
- Phinney's Lane Pump Station
- Backbone of the Town's Sewer Expansion Program









Design Challenges

- Multiple Flow Considerations
- Pipeline Alignment/Corridor
- Herring Run Crossings (Centerville River)
- Connection at Water Pollution Control Facility
- Permitting
- Traffic Management
- Budget Management/Bidding Climate







Catchment Buildout





Flow Planning

PHASE	TIMING	DWELLING UNITS	COMMERCIAL SPACE [SF]	ADF
1A	2026 (2 Yrs)	100	20,000	0.1 MGD
1B	2029 (5 Yrs)	500	25,000	0.6 MGD
1C	2034 (10 Yrs)	3,000	1,200,000	2.8 MGD
2	2044 (20 Yrs)	5,000	1,900,000	4.3 MGD
3	2054 (30 Yrs)	7,000	2,500,000	5.5 MGD
4:6	>2054 (>30 Yrs)	8,000	2,700,000	6.0 MGD



Site Layout



Weston & Sampson

System Hydraulics



Weston & Sampson

System Design



 Optimal channel hydraulics across buildout

- Discharge flexibility
- Future compatibility
- Ease of O&M





Pipeline Alignment/Corridor

- Travelled Way vs. Shoulder
- Existing Utilities
- Gravity Sewer plus Multiple Force Mains
- Traffic Management
- Connection at WPCF





Pipeline Alignment/Corridor

Gravity Sewer plus Multiple Force Mains





Pipeline Alignment/Corridor

Force Main Cleanout Structures



Weston & Sampson

Herring Run Crossings

• Centerville River



Phinney's Lane

Falmouth Road (Route 28)



Herring Run Crossings

• Phinney's Lane Crossing – Test Pit





Herring Run Crossings

- Alternatives Analysis

 Grinder Pump Impacts (Shallow Sewers)
- Deep Sewer Alternative to Minimize Pumps
 - Gravity Sewers approximately 21 feet deep at PS
 - Pump Station approximately 35 feet deep



Connection at WPCF





Connection at WPCF

Coordination with Plant Operations FRIMARY CLARIFIER 114+00 DUAL FORCE 8" 4C 5 MAIN MANIFOLD 62 (SEE 10-SCALE INSET MAP THIS SHEET) WGS 67 PRETREATMENT HEADWORKS BUILDING +_{56.3} 0 0 6* 01 SSD (16) GREASE 12" DI FM (15) RECEIVING STATION 5 6" DI PD (14) in DI FM (13 12" 16" DI FM (12) 12" FG FM (11 12" AC FM (10) 8 20" DI FM (9 DI FM (S) 102 S C (5)



Permitting

Path: !/wse03 local/WSE/Depts/Water/Water Resources Group/015 - Constraints Mapping/Barnstable/1456 Falmouth Rd PS 2020/Emvfrormental Receptor - Barnstable PS ZOOM OUT.mxd User: higginsm Saved: 4/14/2020 10:05:13 AM Opened: 4/14/2020 10:05:16 AM





Permitting

Coordination with MassDOT

 Time of Year and Time of Day Restrictions
 Pavement Replacement Requirements
 Thickness/Width
 CDF Waiver
 Curb Cut at Pump Station
 Traffic Management Plan





Traffic Management

Detour/Traffic Details Planning



Weston & Sampson

Budget Management/Bidding Climate

- Opinion of Probable Construction Cost
- Final Bid Documents

One Contract vs. Two Contracts

- SRF Financing
 - Clean Water SRF Loan Program
 - Principal Forgiveness





Project Schedule

Task	Relevant Date/Completion Date
Design Phase	July 2020 through March 2022
Bid Opening (Route 28 East)	April 13, 2022
Bid Opening (Phinney's Lane PS)	April 20, 2022
Authorization to Award from MassDEP	June 8, 2022
Notice to Proceed	July 22, 2022 (Pump Station) September 13, 2022 (Sewers)
Anticipated Construction Completion (540 day duration, both Contracts)	January 2024 (Pump Station) March 2024 (Sewers)



Budget Management/Bidding Climate

Opinion of Probable Construction Cost

 Route 28 East Sewer Expansion Project: \$12M
 Phinney's Lane Pump Station: \$6.6M
 Total Combined Project Cost Estimate \$18.6M

Bid Results

- Route 28 East Sewer Expansion Project: \$10.2M
- Phinney's Lane Pump Station: \$7.9M
- Total Combined Bid Price: \$18.1M
- Robert B. Our Low Bidder (Both Contracts)





























transform your environment

Final Comments & Questions

westonandsampson.com



transform your environment

Thank You





