Beachmont – Sales Creek Neighborhood Sewer & Drainage Improvements

Angela Moulton
John Viotto


City of Revere, MA

January 25, 2023











PROJECT OVERVIEW AND BACKGROUND

- City of Revere, MA: Dolphin Avenue, George Avenue, Henry Street, and Jones Road
- \$7,000,000 Construction Budget
- F&I New Wastewater Pump Station
- Upgrade 2,800 LF of sewer main
- Rehab. 3,300 LF of drain line
- Redirect 41 private inflow sources
- Full-Depth Road Reconstruction & new concrete sidewalks





BACKGROUND - OVERVIEW AND BACKGROUND

Planning 2010 – 2017

Design 2017 – 2019 Construction 2019 - 2022











BEACHMONT PLANNING / FIELD INVESTIGATIONS

BACKGROUND - PLANNING / FIELD INVESTIGATIONS

- Records review
- IDDE Investigations
- Dye testing
- Smoke testing
- House-to-house private inflow inspections
- CCTV of culvert
- Test Pits for locating utilities
- Boring Program
- Groundwater Sampling
- Road and sidewalk condition inventory
- FEMA Report Evaluation
- Survey





PLANNING - SEWER ANALYSIS

- IDDE Hits
- Illegal Sump Pump Connections
- Shallow sewer = sewer blockages, surcharging, SSOs
- Sewer main higher than services/ sewer service pitching backwards
- Sewer smoke testing
 - smoke in DMH indicates cross connection
 - identified possible sewer sags in multiple areas



PLANNING - DRAIN ANALYSIS

Atlantic Ocean

- Review of FEMA flood plain mapping
- 100 year flood plain elevation = 6'
- Ground elevation = ~5'
- Large drainage culvert installed at nearly flat slope to allow drainage to flow in both directions
- Sales Creek = Outstanding Resource Water; Tributary to an Area of Critical Environmental Concern




Storm-Water PS



PLANNING - BORINGS

- Phase 1 = 8 borings
- Phase 2 = 6 borings + 2 groundwater wells
- Reportable conditions under the Massachusetts Contingency Plan (MCP); Utility-Related Abatement Measure (URAM)
- Groundwater required Remediation General Permit (RGP)
- Layers of peat








BEACHMONT - DESIGN


DESIGN - SEWER

- Lower sewer 3 to 15 FT in areas
- Reverse direction of flow from East to new pump station
- Install 2,800 LF of new sewer
- Raise multiple sewer services on private side to pitch towards street
- Remove sewer services from drainage system





DESIGN - SEWER








NEIGHBORHOOD IMPROVEMENTS (BEFORE)






NEIGHBORHOOD IMPROVEMENTS (ARTISTIC RENDERING)





NEIGHBORHOOD IMPROVEMENTS (AFTER)





Sidewalk




BEACHMONT - CONSTRUCTION



BEACHMONT SEWER SYSTEM UPGRADES

F&I NEW WASTEWATER PUMP STATION

- Constructed SOE & Dewatering System
- Finish Grade Elev. = 6.66'
- Wet Well Floor Elev. = -13.98'
- Wet Well Influent Elev. = -8.77'
- Wet Well Effluent Elev. = -0.18'
- Force-main (240 LF) to discharge to Atlantic Avenue SMH
- Submersible Pressure Level
 Transducer with Ultrasonic & Float
 Back-up





UPGRADES - BEACHMONT SEWER SYSTEM

- R&R 2,800 LF of existing sewer main with new 8" PVC and DI pipe lowering the elevation from 3' to 5-15' below street grade
- F&I new 6" DI Chimneys for deep sewer connections
- R&R 84 Sewer Services (public side), as well as eliminating 2+/- connected to drainage system, and 4 on private-side
- Minimum By-Pass required because existing flow was in the opposite direction.







BEACHMONT DRAINAGE SYSTEM REHABILITATION

UPGRADES - BEACHMONT DRAINAGE SYSTEM


- R&R 1,500 LF of existing drain pipe
- F&I 500+ LF of new drain line
- CIPPL all sections of drain that were in acceptable condition (1,100 LF)
- Multiple point repairs conducted
- Increased average pipe diameter
- Rehabilitate all CBs and install additional CBs
- F&I additional DMHs to increase accessibility to drainage system
- Clean and CCTV/ investigate unknown drainage system areas (1,600 LF)






INFLOW REMOVAL PROGRAM

DISCONNECTED SUMP PUMPS FROM SEWER SERVICES OF INDIVIDUAL PROPERTIES (41) AND REDIRECTED THEM TO THE DRAINAGE SYSTEM (40 – 90 thousand gallons removed per 6-hr storm)









BEACHMONT CONSTRUCTION CHALLENGES

SOIL MANAGEMENT

- Removed 10,000 TONS of Soil
- Soil pre-characterized by area and depth (0-8 ft. & 8-16 ft.)
- Soil Classifications
 - < RCS-1</p>
 - In-State Unlined Landfill (> RCS-1)
 - Out of State Disposal (> Comm 97)
- Separate piles created and stored for additional testing and removal





DEWATERING







UNFORESEEN ISSUE


ENTIRE SEWER MAIN SUPPORTED BY PIER SYSTEM







FULL-DEPTH ROAD RECONSTRUCTION & NEW CONC. SIDEWALKS







BEACHMONT – CONSTRUCTION PHASE SUMMARY

COST: \$1.3M under budget

Construction Cost Estimate: \$6.9M

Construction Cost Actual: \$5.6M

TIME: 3-year period

Sewer and Drainage Work: 15 Months

Sidewalk Upgrade: 6 Months

Road Reconstruction: 1 Month





Q&A

Connect With Us!



Find more insights through our water partnership at cdmsmith.com/water and @CDMSmith



Angela Moulton

CDM Smith

617-452-6561

moultonat@cdmsmith.com

John Viotto

CDM Smith

617-452-6114

viottoja@cdmsmith.com

