NEWEA 2023 Annual Conference Cohas Brook Sewer Project – Phase III Lessons Learned from a 13-year, \$40 million Sewer Expansion Program in Manchester, NH



Frederick J. McNeill, P.E. Robert J. Robinson, P.E. Ian P. Gervais, P.E. January 25, 2023



Agenda

- EPD Organization
- Manchester's Wastewater System
- Cohas Brook Sewer Master Plan
- Phase I
- Phase II
- Phase III
 - Contract 1
 - Contract 2
 - Contract 3
 - Contract 4
- Lessons Learned
- Questions



City of Manchester Facts and Figures

- Settled in 1725
- Evolved from agricultural to industrial 1725 to 1810
- Amoskeag Mills Largest single mill in the world 1915
- Post industrial depression 1930 to 1980's





EPD's Organization Structure

- Created in 1975 City's wastewater utility
- Division of Manchester's Department of Public Works
- An "enterprise"
- Staff of 44
- 15-acre campus 10 Buildings
 - Administration
 - Operations
 - Maintenance





Manchester Wastewater Infrastructure

- 1975: 26 mgd
- 1994: upgrade to 34 mgd
- 2016: upgrade to 42 mgd
- Serves four communities
 - Bedford (4.4%)
 - Goffstown (4.2%)
 - Londonderry (10.2%)
 - Manchester (81.4%)
- Metro population 172,000
- Investing \$75 million over 15 years





Manchester's Wastewater Infrastructure – Pipelines

- 385 miles of sewer
 - 50% "combined" system
 - 11,000 SMHs

E MANC

PROTECTION DIVISION

DEPAR

- 15 CSO outfalls
- 100 miles of pipe, 100 years old or older





Manchester's Stormwater Infrastructure – Pipelines

- 180 miles of drains
 - 14,000 CBs
 - 3,000 DMHs
- Six Urban Ponds







Manchester's Wastewater Infrastructure Pump Stations

- 11 pump stations
- Constructed from 1973 to 2014
- 68 GPM to 25 MGD
- \$6.0M Upgrade from 2011 to 2014





Cohas Brook Sewer Master Plan: Overview

- Cohas Brook "Interceptor Feasibility Plan" (1996)
 - Phase I & II
 - Three (3) Contracts per Phase
- Cohas Brook Master Plan (2010)
 - Phase III
 - Four (4) Contracts





Phase I

- Location
 - WWTP to I-93
- Project Duration
 - 1998 to 2006
- Total Length
 - 21,000 LF
- Total Cost
 - \$19.0M
- Unique aspects
 - Microtunneling under Pine Island Pond
 - Three (3) siphons under Cohas Brook
 - Used existing box culvert under 293/93 split





Phase II

- Location
 - I-93 to Wellington Rd. (State Route 101)
- Project Duration
 - 2007 to 2011
- Total length
 - 25,200 LF
- Total Cost
 - \$12.0M
- Unique Aspects
 - Rt. 28 Bypass under Rt. 101, rolling roadblocks on Rt. 101 for Blasting
 - Deep sewer 30-35'
 - Sewer along and across abandoned railroad bed
 - Candia Rd. Pump Station





Sewer Master Plan

- Completed in 2010 by CDM Smith
- Goals
- Sewer alternatives
- Phase III
 - 12 watershed areas →
 Four (4) Contracts

City of Manchester, New Hampshire

Cohas Brook Sewer Master Plan

May 2010





Phase III

- Project Duration
 - 2010 to 2023
- Total Length
 - 78,800 LF
- Total Cost
 - \$40.0M
- New Customers
 - Contract No. 1 200
 - Contract No. 2 180
 - Contract No. 3 200
 - Contract No. 4 1,000





Contract No. 1 – Overview

- Total Length 20,500 LF
- Total cost \$7.0M
- 2010 to 2011
- Engineer
 - CDM Smith
- Contractor
 - Albanese Brothers
- 200 new customers
- Unique Aspects
 - Narrow streets and ledge
 - Proximity to a major drinking water source
 - Water main replacements







Contract No. 1 - Lake Massabesic





Contract No. 2 – Overview

- Total Length 19,000 LF
- Total cost \$9.0M
- 2012 to 2014
- Engineer
 - Hoyle, Tanner & Associates
- Contractor
 - Park Construction
- 180 new customers
 - Unique Aspects
 - Rt. 101 Crossing Auger Bore with Rock Head
 - Precast Bridge and Box Culvert for stream crossings
 - Gained ownership and utilized existing private sewers
 - Old Sawmill







Contract No. 2 – Auger Bore with A Rock Head under Rt. 101





Contract No. 2 – Auger Bore with A Rock Head under Rt. 101







Contract No. 2 – Precast Bridge





Contract No. 3 – Overview

- Total Length 14,300 LF
- Total cost \$8.0M
- Engineer
 - Kleinfelder
- Contractor
 - Park Construction
- Construction duration
 - 2014 to 2016
- 200 new customers
- Unique Aspects
 - Siphon under Cohas Brook
 - Construction on a State Road





Contract No. 3 – Siphon





Contract No. 3 – Cohas Brook Bypass





Contract No. 3 – State Road (NHDOT)





Contract No. 4 – Overview

- Total Length 19,000 LF
- Total cost: \$16.0M
- Engineer
 - Kleinfelder
- Contractor
 - Park Construction
- Construction duration
 - 2021 to Present
- 1,000 new customers
- Unique Aspects
 - Existing private sewer utility
 - New metering station





Contract No. 4 – Overview (cont.)





Contract No. 4 – Easement Acquisition





Contract No. 4 – Construction Challenges









Contract No. 4 – Aaron Drive Metering Station

- Prefab concrete
 structure
- Below grade vault
- Parshall flume





Contract 4 – Roadway Restoration





Phase III – Summary

New Customers Costs (Millions)

Contract No. 1 – 200\$7.0Contract No. 2 – 180\$9.0Contract No. 3 – 200\$8.0Contract No. 4 – 1,000\$16.0



Total 1,580 \$40.0

Lessons Learned

- 1. Easements
- 2. Leveraging of Funds
 - Bike Lanes
 - Drainage Improvements
 - Roadway Reconstruction and Curbing
- 3. Be prepared and Plan for the unexpected
 - Crossing under Rt. 101
 - Private utilities and sewer systems
- 4. Maximize gravity sewers to try and eliminate or not construct pump stations
- 5. Seek public input and learn to listen



Lessons Learned (Continued)

- 1. Long-term Vision
 - Financing
 - Engineering
 - Political and Public Support
 - Resources



- 2. Long-term Investment
 - Time
 - Rate Increases
 - Internal Staffing

Acknowledgments

Frederick J. McNeill, P.E. Robert McCoy, P.E. McKenna Dunn Aaron D'Amario







Contact Information

Frederick J. McNeill, P.E., <u>fmcneill@manchesternh.gov</u>, 603-624-6341

Robert J. Robinson, P.E., rrobinson@manchesternh.gov, 603-624-6526

Ian Gervais, P.E., IGervais@kleinfelder.com, 207-694-2808



Thank you for your time