

Keeping the aeration train rolling through turbulent times: Hampton's WWTP upgrades


NEWEA Annual Conference

January 2023

Phil McHenry, EIT
Mike Carle, Chief Operator



Welcome to Hampton, NH



Source: Google Earth

- Hampton Beach
 - Popular Tourist Destination
- Year-round population: ~16,000
- Seasonal Population Swings
 - Holiday Surges (Memorial Day, July 4th, Labor Day)
 - Seafood Festival (150,000 people!)
- Seasonal Wastewater Flows and Loads

Hampton Wastewater Treatment Plant (WWTP)



Source: Google Earth

- Originally constructed in the 1920s
 - Major upgrades in the 1960s and '70s
- 2.5 MGD average daily flow
 - 4.7 MGD design flow
- 12 MGD + peak flow conditions
- Discharges to tidal tributary
- Significant recreational resources...
 - Shellfishing beds
 - Popular beach
 - Recreational/commercial fishing
 - Boating

Need for WWTP Upgrades



Source: Google Earth

- **No comprehensive upgrade in 45+ years!**
 - Existing Structures date from 1960s and '70s
- **Equipment in critical condition/obsolete**
 - Clarifier/thickener mechanisms
 - Influent pumps
 - Grit System
- **Aeration System**
 - Approaching loading limits
 - Diffuser grid failures
 - Ageing blowers
 - Limited process control & automation
 - Gates & valves inoperable
 - No flexibility for seasonal load swings

Project Timeline



Phase 1 – Scope of Work



- **Aeration System Upgrades**
- **New SCADA System**
- **Comprehensive PLC/Control Panel Upgrades**
- **Headworks Upgrades**
- **Influent Pump Station Upgrades**
- **Mixed Sludge Pump Station Upgrades**
- **Plant Water Pump Upgrades**
- **Primary Clarifier & Gravity Thickener Rehab**
- **Plant-wide Electrical & HVAC Upgrades**

Aeration System Upgrades



Aeration Tanks

- Tank modifications & baffle walls
 - Single train to Two trains, operational flexibility
- Submersible mixers & internal recycle pumps
- New fine bubble diffusers, gates, & valves
- Instrumentation & controls
 - Enhanced process automation & efficiency




Blower Building

- Aeration blowers
 - Improved efficiency & energy savings
- Blower building control panel
- Ventilation improvements
- Emergency standby power generator

The Aeration Train

The Existing System




Source: Google Earth


- Originally Designed as Activated Sludge Process (Nitrification)
- Retrofitted to MLE Process (Denitrification)
- Single Train, 4 Tanks
 - Configured for MLE
- Limited Operational Flexibility
 - Gates between tanks no longer functional
 - No way to take any single tank offline

The Aeration Train Design

Existing – One Train




New – Two Trains




The Aeration Train Design

Existing Tanks




Tank Modifications



The Aeration Train Design


Existing Tanks



Filled in
Effluent
Channels




Tank Modifications




The Aeration Train Design

Summer Configuration – MLE




Winter Configuration – MLE




The Aeration Train Design

The $\frac{3}{4}$ Configuration – MLE



Additional Capacity – Full Nitrification



Challenges: Construction Sequencing



- **Getting into the Tanks**
 - Isolating Tanks from the flow
- **Working around the Treatment Process**
 - Managing flow, maintaining capacity
 - Bypass Pumping required? (\$\$\$)
- **Unknowns**
 - What happens when we take 2 tanks offline? (50% capacity)
 - How long can we run at reduced capacity?
 - How will the process react?
 - What's under the water (i.e., cracks?)
- **Blower Building Sequencing**
 - Replacing blowers & aeration piping
 - ...while Continuously Providing Air


Challenges: Plant Operations



- **How will the process react?**
 - What happens when we take 2 tanks offline?
 - How long can we run at reduced capacity?
 - How will the bugs perform? (WWBD?)
 - Need to continue to meet permit limits
- **MLE to Full Nitrification Process**
 - Without denitrification, low alkalinity, pH...
- **Reduced Capacity**
 - Maintaining Biomass and Sludge Retention Time (SRT) to treat Influent Loading
 - How many tanks do we *really* need?

Understanding The Aeration Train


Follow the Nitrogen




Source: Google Earth

- How many tanks do we *really* need now?
 - Look to the data!
 - Follow the Nitrogen through the process
- Years of data from each of the four tanks
 - Ammonia (NH_3)
 - Nitrite (NO_2^-)
 - Nitrate (NO_3^-)
- When loading is low, most of the Ammonia & BOD is consumed in Tanks 5 and 2


Influent BOD Loading (Biochemical Oxygen Demand)



Influent BOD Loading (Biochemical Oxygen Demand)




Construction Challenges



Obstacles to Isolating the Tanks

- Existing Slide Gates
 - Inoperable, leaking
- Existing Ports between Tanks
 - Always Open Port between Tanks 2 & 5
- Cutting through Walls into Active Tanks
 - Slide Gates in the Influent Chanel
 - Internal Recycle (IR) Piping between Tanks 1-2 and Tanks 4-5
 - New Slide Gate between Tanks 2-5
- How do you cut through a wall, without draining the water on the other side?

The Original Sequencing Plan




The original plan entailed...

- Working in One Tank at a time
- Bypass Pumping the Influent Channel to Install Slide Gates
- Work in Tank 1
- Work in Tank 4
- Drain Tanks 1 & 2 *briefly* to core IR Piping
- Drain Tanks 4 & 5 *briefly* to core IR Piping
- Bypass Pumping to *briefly* Drain Tanks 2 & 5 to install new Slide Gate
- Work in Tank 2
- Work in Tank 5

... A fair amount of process juggling and bypass pumping!

Construction – Fall 2020


Tank 1



- **Block Flow to Tank 1**
 - Flow briefly diverted to Primary Clarifier
- **Temporary Cofferdam in Influent Channel**
 - Enabled Slide Gate Installation w/o Bypass

Construction – Fall 2020


Tank 1



- **Isolate and Drain Tank 1**
 - Plug Openings to Online Tanks
 - Seal leaking Cracks & Construction Joints
- **Clean Up and Demolish**

Construction – Fall 2020


Tank 1



- **Concrete Work**
 - **Construct Baffle Wall**
 - **Fill Effluent Channel**

Construction – Fall 2020


Tank 1



- Submersible Mixer
- IR Piping
- Valves
- Diffusers & Air Piping
- Electrical Work

Construction – Winter 2020-21



Tanks 2



- **Town gives Penta Tank 2**
 - Need to Core IR Piping between Tanks
- **With only 1/2 of the train**
 - Process doing surprisingly well
 - Need to blow off excess air

Construction – Winter 2020-21


Tank 2



- **Plug & Plate Opening to Tank 5**
 - No gate here – always open!
- **IR Piping & IR Pump**
- **Install Cofferdam**
 - Enabled future installation of Slide Gate, without draining Tanks 2 & 5 simultaneously

Construction – Spring 2021

Tank 2





- **Gates & Valves**
- **Diffusers & Air Piping**
- **Electrical Work**
- **Working against the clock into springtime**
 - **Loads on the rise...**

Temporary Blower Building



Construction – Fall 2021


Tank 3



- Repeat for Train 2
- Switch Cofferdam to other side of Influent Channel
- Treatment Process now operating the new Train 1

Construction – Fall 2021


Tank 3



- The next wall goes up

Construction – Winter 2021-22


Tank 4



- **Cracks in Concrete**
 - Construction Joints
 - Foam Injections
- **Ice Buildup in Tanks**

Construction – Spring 2022

All Aboard the Aeration Train!



- **Both Trains Completed Spring 2022**
 - Several months ahead of Planned Completion

Lessons Learned



- **Be flexible**
- **Maintain close communication and cooperation between Town, Contractor, and Engineer**
 - Enabled greater flexibility and creativity in sequencing approach
- **Understand the WWTP and process needs**
 - Enabled us to reevaluate plant capabilities and process requirements in real time
- **... and consider using cofferdams to avoid bypass pumping!**

The next Phase of
improvements is underway...
See you next year!

Acknowledgements



- Jennifer Hale
- Michael Dube
- Michael Carle
- Joseph Lynch



- Robert Helgesen
- Bill Ouellette
- Carlin Berger
- Dave Spaulding



- Michael Curry
- Paul Denis
- Kyle Allcroft
- Steve Soule

THANK YOU

Contact Information



Phil McHenry

philip.mchenry@wright-pierce.com
978.416.8029



Mike Carle

mcarle@hamptonnh.gov
603.758.1299

Influent BOD 2012-2022

