



HOW BANGOR, MAINE EXPANDED A 20-YEAR-OLD STORAGE FACILITY THREEFOLD ALONG A VIBRANT WATERFRONT

Greg Heath, AECOM

Amanda Smith, City of Bangor Director of Water Quality Management John Theriault, City of Bangor Engineering Department Kate Mignone, AECOM

June 8, 2023

Agenda

- Background
- Davis Brook Storage Tank (DBST)
 - Design
 - Construction
 - Commissioning
- Conclusions





Background



Location Plan



Community Setting

- Located on Penobscot River at confluence with Kenduskeag River
- Older "Working" City with long history in lumber and trade
- Population 31,921 (2021)







Wastewater Collection System

- Service Area: 33 Mi²
- Population Served:
 - 31,900 in Bangor
 - 8,000 in Connected Communities
- 157 Miles of Gravity Sewer
- 9 Miles of Interceptor
- 4,000 Ft. of Force Main
- 5 Pump Stations
- 8 Siphons
- 9 Permitted CSOs



Clean Water Act Compliance Milestones

30-Year History Working With EPA & ME DEP on CWA Compliance

- 1987: CD with ME DEP to begin CSO control
- 1991: CD with EPA for CSO LTCP I
- 1994: EPA accepts LTCP I
- 2009: All LTCP I projects complete
- 2012: DRAFT PHASE 2 LTCP
- 2013: Negotiation begins on new CD
- 2015: New CD finalized
- 2017: PHASE II LTCP

First 2017 LTCP Project - Davis Brook Storage Tank

- Project drivers:
 - Frequency and volume of overflows at the Davis Brook CSO
 - Location of the proposed DBST in the vicinity of the Waterfront
 - Coordination with other Waterfront development plans
 - Opportunity to improve hydraulics at the existing Davis Brook CSO regulator structure



Davis Brook Storage Tank Design & Construction



Design Criteria

- O.F. target: 4 per year
- Storage required: 5 MGAL
- Existing conduit: 1.2 MGAL
- Tank storage: 3.8 MGAL
- TOTAL SYSTEM: 5.0 MGAL



New Regulator Structure

- Separate contract from DBST
- Increased dry weather connection size
 - 30 & 21 inch to 42 inch
- New hydraulically-actuated gates for flow isolation and control
- Detect overflow and measure flow over weir



DBST Site Access Challenges





Connection Between Conduit and Tank

- Twin 48-inch ductile iron pipes
- Sized to meet 4 overflow per year level of control
- Included two joints in each pipe to account for potential differential settlement





Siting Considerations



Siting Considerations



Tank Geometry and Key Features

- Length: 116 ft. Freeboard: 3.1 ft.
- Width: 242 ft.
- Side water depth: 20.5
- 242 ft. Longitudinal slope: 1%
 - 20.5 ft. Gutter cross slope: 2%







Tank Dewatering

Dewatering Pump Design

- Empty each cell that fills following CSO events
- Empty water from tipping buckets following postevent flushing
- Empty infiltration to maintain low level in each cell between CSO events
- Three installed pumps (one per cell) plus shelf spare
- Part of automated post-event clean-up sequence
- Sized to:
 - Operate over full range of water levels in tank
 - Dewater full tank in 24 hours





Tipping Bucket Design

- Clean the floor of the DBST following storm events
- Flush debris to tank sump for removal by dewatering pumps
- Three tipping buckets per cell
- Part of automated post-event clean-up sequence:
 - Dewatering pumps empty each cell containing storm flow
 - Tipping buckets sequentially fill and tip
 - Dewatering pumps empty gutter and sump after each tipping bucket tips



Tank Vent

- Capable of exhausting air during tank filling
 - Sized based on peak flow into tank
- Admits air into tank when emptying
- May add odor control in future if warranted



Other Design & Construction Challenges

- Support of excavation
- Groundwater control
- Presence of competent rock
- Contaminated soil
- Construction testing
- Facility start-up and acceptance testing







Commissioning



Sequence of Commissioning Activities

- Physical check-out
- Field testing
 - Testing by contractor, with supplier assistance
- Start-up
 - Clean water testing
- Commissioning
 - Process flows actual CSO





Equipment / Systems

- Chopper pumps
- Slide gates
- Tipping buckets
- Electric actuators
 - Running test in presence of Engineer
 - Run without vibration or jamming
 - At speeds specified
 - Observe / record motor inputs
 - Observe proper valve / gate positioning



ADANGER

120 VOLTS

130 Terrs

MERGENC' STOP



Commissioning

- Stage 1
 - HVAC system operates as designed, minimum 5 days continuously
 - SCADA system operates as designed, minimum 5 days continuously
 - Electrical equipment operates as designed, minimum 5 days continuously
 - Dewatering pumps operate as designed to pump infiltration (if required)
 - A qualifying storm event (cell 3 at least half fills) occurs and system operates as designed
- Stage 2
 - HVAC, SCADA, electrical, and dewatering equipment continue to operate as designed until second qualifying storm event occurs
 - Second qualifying storm event (same criteria as first event) occurs, and system operates as designed

Conclusions



Conclusions and Take-Aways

- Importance of designing CSO facilities for future expansion
- Importance of planning for commissioning of intermittent duty wet weather facilities
- Innovative approach for expanding CSO storage with integrated storage solution
- Collaboration within City to meet needs of CSO control and future waterfront expansion







DAR



Questions?

