

The Portland Back Cove West CSO Storage Conduit

Collaborating to Protect our Water Resources

January 2024


Ryan Wingard, PE – Wright-Pierce
Steve Guerrette, PE – Wright-Pierce



Presentation Overview

History (City's LTCPs)
Design Process
VE Process
Construction Progress
Additional Project Details
Lessons Learned
Project Performance
Thank You

History (City's LTCPs)


IMPORTANT UPDATES

Masking in Indoor Places Recommended When County Reaches Substantial Community Transmission
[Read On...](#)


PORTLAND | me
PAY & APPLY
GOVERNMENT
SERVICES
BUSINESS

| | | Combined Sewer Overflow and Long Term Control Plan Reports |
|--------------------------------|---|--|
| CAPISIC BROOK WATERSHED | + | <ul style="list-style-type: none"> CSO 1991 MEDEP Administrative Consent Agreement ← CSO 1993-12 Abatement Study Master Plan Final Report ← CSO Tier II 2003-02-05 Final Report ← |
| STORMWATER SERVICE CHARGE | + | <ul style="list-style-type: none"> CSO 2008-10-23 MEPDES Permit ME0101435 Final CSO 2011-05-04 MEPDES Permit ME0101436 Minor Revision |
| RAIN GARDENS IN PORTLAND | + | <ul style="list-style-type: none"> CSO 2010 Annual Progress Report Portland, ME CSO 2010 Annual Activity and Volumes Portland, ME CSO 2011 Annual Progress Report Portland, ME CSO 2011 Annual Activity and Volumes Portland, ME |
| SEWER ABATEMENTS | | <ul style="list-style-type: none"> CSO 2012 Annual Progress Report Portland, ME CSO 2012 Annual Activity and Volumes Portland, ME CSO 2013 Annual Progress Report Portland, ME CSO 2013 Annual Activity and Volumes Portland, ME |
| SUBMETER PROGRAM | | <ul style="list-style-type: none"> CSO 2013 Annual Progress Report Portland, ME CSO 2013 Annual Activity and Volumes Portland, ME |
| FATS, OILS, AND GREASE PROGRAM | + | <ul style="list-style-type: none"> CSO 2013-01-25 LTCP Tier III Update Final Report ← CSO 2014 Annual Progress Report Portland, ME CSO 2014 Annual Activity and Volumes Portland, ME CSO 2014-03-04 MEPDES Permit ME0101435 Final CSO 2015 Annual Progress Report Portland, ME CSO 2015 Annual Activity and Volumes Portland, ME CSO 2016-03-01 Historic Annual Flow Volume Table For 2015 CSO 2016 Annual Progress Report Portland, ME CSO 2016 Annual Activity and Volumes Portland, ME CSO 2016 Annual Activity - Volumes Portland, ME CSO 2017 Annual Progress Report Portland, ME CSO 2017 Annual Activity and Volumes Portland, ME CSO 2018 Annual Progress Report Portland, ME CSO 2018 Annual Activity and Volumes Portland, ME CSO 2019 Portland CSO Activity and Volumes CSO 2019 Portland Annual CSO Progress Report CSO 2020 Annual Progress Report Portland, ME CSO 2020 Annual Activity and Volumes Portland, ME |
| SEWER REHABILITATION | | |
| DEWATERING PROGRAM | | |
| STREET SWEEPING | | |
| WASTEWATER MAINTENANCE | | |
| REPORTS AND ASSESSMENTS | | |
| GREENER NEIGHBORHOODS | | |

- 1991 – Consent agreement
- 1993 – Master plan
- 2003 – CSO Tier II
- 2013 – CSO Tier III
- Continued annual progress reports
- Continued annual volumes report

<https://www.portlandmaine.gov/1835/Reports-and-Assessments>

History (City's LTCPs)




- **Capture first flush – first 1” of storm**
 - 80% of storm volume
 - 90% of pollutant load
- **Provide flexibility**
- **87% CSO volume reduction**
- **Storage as primary element**
- **Initial focus on Back Cove**
- **Integrate with facility upgrades**
- **Replace aging infrastructure**

<https://www.portlandmaine.gov/1835/Reports-and-Assessments>

<https://www.portlandmaine.gov/1835/Reports-and-Assessments>

Design Process




- Initial work began in late 2014
 - Field data collection
 - Flow metering
 - Preliminary InfoSWMM modeling
 - Preliminary geotechnical explorations
 - Conceptual layout
 - Green infrastructure/ separation project report
- 2016 work halted

Design Process

- 2016 – 2018
 - City completed separation/GI projects
 - Additional planned separation
- 2017 estimate impact of separation and LID using InfoSWMM
- Supported a reduced storage volume
 - Maine DEP approved 2.25 MG vs. 3.5 MG
- Eight CSO points down to two CSO points
- Given “go-ahead” in 2018
 - Developed preliminary design package




Design Process




- Compile background technical documents
- Baseline project information
 - Geotech
 - Wetlands
 - Property surveys
 - Dartmouth Street
- PDR
- Preliminary specifications
- 30% layout plans
- Review sent to City

Design Process




- 2019 request to develop final design and bid set
- Supplemental geotech investigations
- Geotech design memo
- Hydraulic modeling
 - InfoSWMM
 - CFD modeling (slope, F&E, venting)
- Traffic plans
- Preparation of 50%, 90%, and bidding

Design Process




- 3,150 LF 8'x10'
- 600 LF of 8'x12'
- Drainage
- Vertical profile
- December 2020
 - Issued for bid
- Awarded to Sargent Corporation

VE Process




- March 2021
- Additional ledge probes and investigation by Sargent Corporation
- Higher than planned ledge
 - 12,200 CY bid
- Request for a VE option
- Bulk of storage at downstream end
 - Less ledge

VE Process




- 1,690 LF of double-barrel 8'x10' box
 - 1.93 MG
- 1,975 LF of 60"
 - 0.29 MG
- 315 LF of 48"
 - 0.03 MG
- Total Length: 3,980 LF
 - Total Storage: 2.25 MG

VE Process



VE Process




A1 NOTES:

- DESIGN SECTIONS A1-1 AND A1-2 REPRESENT THE MINIMUM AND MAXIMUM BEDROCK ELEVATIONS ALLOWED FOR THE TEMPORARY SUPPORT OF EXCAVATION DESIGN SECTION A1. NOTIFY G2A IF CONDITIONS IN THE FIELD VARY FROM THE SUBSURFACE CONDITIONS CONSIDERED FOR THIS OR ALL OTHER DESIGN SECTIONS SHOWN ON THESE PLANS.
- REFER TO THE TEMPORARY SOE STATIONING AND INTERNAL BRACING FOR THE APPROXIMATE LOCATIONS FOR DESIGN SECTION A1.
- MICROPILE CASING SEGMENTS BELOW BOE SHALL BE 10'-0" MINIMUM IN LENGTH. JOINTS ARE NOT PERMITTED BELOW BOE ELEVATION.


A2 NOTES:

- DESIGN SECTIONS A2-1 AND A2-2 REPRESENT THE MINIMUM AND MAXIMUM BEDROCK ELEVATIONS ALLOWED FOR THE TEMPORARY SUPPORT OF EXCAVATION DESIGN SECTION A2. NOTIFY G2A IF CONDITIONS IN THE FIELD VARY FROM THE SUBSURFACE CONDITIONS CONSIDERED FOR THIS OR ALL OTHER DESIGN SECTIONS SHOWN ON THESE PLANS.
- PUSH-AND-DIG METHOD OF CONSTRUCTION SHALL BE UTILIZED FOR DESIGN SECTION A2.
- BRACE LEVEL 2 ELEVATION WILL VARY (MAX. EL. +7.0; MIN. EL. +3.5) BASED ON TOP OF BEDROCK ELEVATION OBSERVED IN THE FIELD. WHEN BEDROCK IS ENCOUNTERED ABOVE EL. +0.5, THE MAXIMUM UNSUPPORTED HEIGHT OF 3'-0" SHALL BE MAINTAINED BELOW THE BOTTOM BRACE AS SHOWN ON DESIGN SECTION A2-2. WHEN BEDROCK IS ENCOUNTERED AT OR BELOW EL. +0.5, BRACE LEVEL 2 SHALL BE INSTALLED AT EL. +3.5 AS SHOWN IN DESIGN SECTION A2-1 AND THE MAXIMUM UNSUPPORTED HEIGHT OF 6'-6" SHALL BE MAINTAINED BELOW THE BOTTOM BRACE AS SHOWN ON DESIGN SECTION A2-1.
- REFER TO THE TEMPORARY SOE STATIONING AND INTERNAL BRACING FOR THE APPROXIMATE LOCATIONS FOR DESIGN SECTION A2.



| | | | | | | |
|--|---|------------|-----|------|------------|----|
| 0 | 2 | 4 | 6 | 8 | 10 | 12 |
| SCALE: 1/4"=1'-0" | | | | | | |
| REV | | DATE | BY | CHKD | DATE | |
| 1 | | 07/02/2021 | AWB | RT | 07/02/2021 | |
| <p>BACK COVE WEST STORAGE CONDUIT PORTLAND, MAINE</p> <p>TEMPORARY SUPPORT OF EXCAVATION SECTION VIEW 1 OF 3</p> <p>PREPARED BY: GZA Geo-Environmental, Inc. Engineers and Scientists www.gza.com</p> <p>DESIGNED BY: RMC DRAWN BY: GR SCALE: AS NOTED</p> <p>PROJECT NO. 09-0028107.00 REVISION NO. 0</p> <p>DRAWING ES-10 SHEET NO. 11 OF 13</p> | | | | | | |

VE Process



- Overall, the VE was estimated to save approximately \$0.75 million
- Estimated to save nearly 6,000 CY of rock excavation

Construction Progress



Construction Progress



Construction Progress



Construction Progress



Construction Progress



Construction Progress




Construction Progress



Construction Progress

- Last box installed October 2022
- SAT testing completed May 3rd
- Conduit in service end of May 2023
- Baxter surface pavement completed September 2023
- Substantial completion in October 2023
- Ongoing punchlist work underway
- Final completion anticipated for summer 2024



Additional Project Details

- **Environmental permitting**
 - **Maine DEP – permit by rule**
 - **ACOE – individual permit**
- **City historic preservation (cobblestones/trees)**
- **Stakeholders**
 - **PWD – BBPS**
 - **Nearby homes**
- **Challenges**
 - **Shallow bedrock/ledge elevations**
 - **Very little elevation change**
 - **Conduit settling**
 - **Conduit waterproofing (over 200 joints)**



Lessons Learned

- Pre-construction public outreach doesn't prevent public concerns during construction. Had daily/weekly updates.
- Benefited from contractor and internal constructability reviews.
- Initially scoped 2 RPRs because of project length...outside the box thinking for transportation reduced to 1 RPR.
- Expect the unexpected (i.e., police chases and attempted break-ins).
- Collaborative team effort between City, contractor, and engineer was necessary for a successful project.



Project Performance

- Performance to date (since June 1, 2023)
 - Six overflows closed, two remain
 - Between June 1st and September 20th, 14 potential CSO precipitation events with four overflow events
 - Additional weir modifications needed to help capture additional volume
 - Removing up to 2.25 MG of overflow from Back Cove for each event
- Currently operating in “manual,” draining their two tanks separately
 - Goal is to have the CSO storage facilities drain via a single intervention using SCADA



Community Success

Final Striping



Baxter Boulevard Reopening Party



City of Portland: Nathaniel Smith, Bill Boornazian, Brad Roland

Sargent: Glenn Adams, Doug Morrison

Portland Water District: Adam Sellick, Charlene Poulin

THANK YOU

Contact Information



Ryan Wingard, PE

ryan.wingard@wright-pierce.com
207.523.1419



Steve Guerrette, PE

steve.guerrette@wright-pierce.com
207.319.1504