


Collaborative and Innovative Efforts for Fast- Track Projects



January 29, 2025



Our Speakers




Joel Jones, PE
Portland Water District
Project Manager



Stephanie Hubbard, PE
Kleinfelder
Project Manager



Jose Infante Corona, PE
Kleinfelder
Technical Design Lead



Gil Hogan, PE
Kleinfelder
Assist. Project Manager

Agenda



OVERVIEW OF PWD
AND PROJECT



DESIGN & KEY
DECISIONS




EVALUATION OF
PERFORMANCE



Q&A
DISCUSSION

Portland Water District



186 Employees



56,114 services with a 140 sq
mile service area




21 MGD of Water Delivered
1,010 miles water mains
5,197 hydrants




115 miles wastewater pipe
76 WW Pump Stations
4 WW Treatment Plants

East End Wastewater Treatment Facility (EEWWTF)



- Maine's largest treatment facility
 - Constructed in 1979
 - Secondary clarifiers upgraded once in 1999
 - Population Served: 60,000
- Flow: (million gallons per day)
- Average: 19.8
 - Peak Flow: 80.0


EEWWTF Upgrade Project



Primary Gallery Upgrade:

- Primary Sludge Gravity Thickener
- Primary Sludge Pumps
- Plant Water Pumps and VFDs
- Plant Water Strainer
- New SCADA Panel
- Primary Sludge Pipe Modifications
- Electrical Upgrades/new MCCs
- Upgrades to Primary Electrical Room
- Upgrade to Instrumentation and Controls

EEWWTF Upgrade Project



Secondary Clarifier Upgrade:

- Replacement of mechanism with SS 316 spiral rake
- Replacement of existing influent slide gates to secondary clarifiers with SS 316 slide gates
- Replacement of plant water suction pipe isolation valves
- Concrete Repairs to clarifiers
- Electrical Upgrades
- Instrumentation and Control Upgrades

Operational Challenges



- **Decreased allowable inventory levels**
 - Lower solids loading rate to clarifiers
 - Unable to implement nutrient optimization efforts (to resume in 2025!)
- **Decreased RAS capacity**
 - Each clarifier is dedicated to a specific pump
- **Concerns over additional failures during construction**
 - What if one of the two functioning clarifiers fails while third clarifier is under construction?

Project Schedule

Preliminary Design

February - May 2023

Key Deliverables:

- Pre-Procurement Package
- Preliminary Design Report

Final Design

May - October 2023

Key Deliverables:

- 90% Milestone and Workshop
- 100% Milestone
- Early Demo Package – SC#3
- Bidding and Award

Construction

October 2023 – April 2025

Key Milestones:

- Nov 2023 - Early Demo of SC#3
- April 2024 - SC#3 Online
- August 2024 - SC#2 Online
- December 2024 - SC#1 Online

Key-Design Decisions for Fast-Track



Project partnership and collaboration


- Weekly Check-In Meetings
 - Owner and OPM
 - Design Engineer and Subconsultants
- Design Milestones/Workshops



Key-Design Decisions for Fast-Track

Pre-Procurement

- Secondary Clarifier Mechanism
- Slide Gates
- SCADA Panels
- What about Electrical Equipment?




Key-Design Decisions for Fast-Track



Contractor Coordination

- Early Demolition Package for SC#3
- Contractor and Sub-Contractor Informational Meeting
 - Early Outreach on project and schedule
- Contract “Novation” discussed



Performance: Secondary Clarifier Mechanism Old vs New


- The main differences are:
 - Energy Dissipation Inlet (Better inlet flow conditioning)
 - Anti-rotational Baffle (Better scum removal)
 - RAS Pipe Inlet
- Comparison for Two (2) clarifiers Old Mechanism Vs. Two (2) clarifiers New Mechanism

Performance: Secondary Clarifier Mechanism Old vs New

With Old Mechanism



With New Mechanism



Performance: Secondary Clarifier Mechanism Old vs New





FIGURE 8.13 Flocculating energy dissipating feedwell (FEDWA).





Performance: Secondary Clarifier Mechanism Old vs New

Comparison of Clarifier Performance Pre-Upgrade Vs. Post-Upgrade

Parameter	Units	Pre-Upgrade	Post-Upgrade
Time Period	Date	04/01/23 to 07/31/23	08/01/24 to 11/14/24
Avg. Flow	MGD	17.2	11.14
Max. Flow	MGD	66.1	78.3
Air Temp. Range	*C	-4 to 29	-7 to 26
Avg. Air Temperature	*C	12.2	9.9
Avg. Effluent Turbidity	NTU	7.2	3.8
Avg. Total Suspended Solids	mg/L	17.6	10.3

PERFORMANCE: SECONDARY CLARIFIER MECHANISM OLD VS NEW

Turbidity Over Time – Normal Operations




Flow Vs. Turbidity Scatter Plot


- Flows between 15 and 30-MGD
- No Polymer added, No wet weather effect.
- Comparison of Post-Upgrade and Pre-Upgrade
- Plot of Flow (MGD) Vs. Effluent Turbidity (NTU)

Flow Vs. Turbidity Scatter Plot



Flow Vs Turbidity Pre-Upgrade




Flow Vs Turbidity Post-Upgrade



Performance: Future RAS Pumping



Construction Progress



Construction progress



Public Education

WHAT AM I LOOKING AT?



EAST END WASTEWATER TREATMENT FACILITY SECONDARY CLARIFIERS




WHAT ARE SECONDARY CLARIFIERS?

These three clarifiers are essential to the operation of the treatment facility. They provide an opportunity for solids to settle out so that the water is clean and ready to be sent to Casco Bay after disinfection.

The nearly 25-year-old equipment will be replaced with more modern stainless-steel equipment.

WHAT'S GOING ON?

Portland Water District is enhancing the treatment facility's efficiency and operation with modern equipment to replace the 25-year-old secondary clarifiers. This essential upgrade plays a direct role in our ongoing efforts to ensure Casco Bay remains clean and healthy. This work is part of a \$5 million investment to upgrade the secondary clarifiers and other process equipment at this facility. We consistently invest in our infrastructure to ensure efficient and effective operations.



Scan the QR code below with your smartphone for a virtual tour of the facility!



DID YOU KNOW?

The weight of the stainless-steel equipment that will eventually be installed in each one of the three secondary clarifiers totals to more than **45,000 pounds**. That's the equivalent of **40 bull moose**!



Educational Poster/Sign installed along the Eastern Promenade Trail

What Success Looks Like



Portland Water District
Portland, ME



AEC ENGINEERING
AUTOMATION & ELECTRONIC CONTROLS



Woodard & Curran



B·H·MILLIKEN
Electrical Contractors