



# City of Fall River

## Solids Handling Optimization

**Megan Moody**  
CDM Smith

**Paul Ferland**  
City of Fall River

**Jonathan Mongie**  
Inframark

November 18, 2025






# Agenda

1. Planning
2. Design and Construction
3. Operations





# Planning





# History

- 1857-1948 Direct discharge to receiving waters
- 1948-1952 Sewer outfalls converted to CSO outfalls with initial construction WWTF
- 1978-1980 Secondary Treatment Upgrade
- 1997-2000 Wet Weather Capacity Upgrade
  - Dry weather flow = 50 MGD
  - Wet weather flow = 106 MGD
- 2021 Site Electrical and Incinerator Demolition
- 2025 Solids Handling Upgrade



# Planning Documents


- 2015 Integrated Plan
  - Balance infrastructure needs (CSO, sewer, drainage, treatment, water), operation concerns, regulatory requirements, public health and safe issues and financial constraints of the community.
- 2018 Wastewater Facilities Plan
  - Build upon the Integrated Plan to develop phased implementation of upgrades to the treatment facility





# Wastewater Treatment Facilities Plan


- Phased upgrade approach
  - Aging infrastructure
  - Reliability of operations
  - Potential permit modifications
  - Solids handling alternatives
  - Incinerator shutdown







# Design & Construction





# WWTF Contract No. 1

## Site Electrical Upgrade and Incinerator Demolition

### ■ Electrical Site Work

- Reliable electrical infrastructure to support process and building facilities



### ■ Incinerator Demolition




- Permit modifications required abandonment of incinerator in 2016
- Demolition required to move forward with future solids handling facilities





# WWTF Contract No. 2 - Solids Handling Upgrade

## Pre-Upgrade Solids Process




- Co-thickening GTs
- Mainly liquid hauling 1.5-3% solids
- Limited cake disposal options







# Process Flow Diagram





# Gravity Thickener Complex

- Upgraded Configuration
  - 2 GT tanks for primary sludge thickening only
  - 1 WAS storage tank (dual ring)
  - 1 thickened sludge storage tank (dual ring)
  - Odor control system
  - Pumping systems
  - Dome covers
- Improved quality of thickened sludge
- Improved operations flexibility
- Reduce odors



# Solids Handling Building

- Upgraded Configuration
  - 2 Gravity Belt Thickeners
  - 2 Belt Filter Presses relocated above cake dumpsters in lieu of long conveyors
  - Garage expanded for larger containers
  - New chemical feed systems
  - New odor control systems
    - GBT direct connection
    - BFP room connection





# Facility Support Spaces

## ■ Operations Building

- Laboratory
- Locker rooms
- Office spaces
- Control Center
- Lunchroom



# Facility Support Spaces

- Administration Building
  - Management Staff
  - Training Center





# Maintenance of Plant Operations during Construction

- Maintain thickening, odor control and liquid truck hauling
- Phased construction sequencing
  - SSTs upgrade, BFP demo, temporary thickening system
    - ↳ GT upgrade, GBT install
    - ↳ BFP install, conveyance and garage bay
  - Operations building construction
    - ↳ Administration building renovation
    - ↳ Site work
- Temporary Systems
  - RDT, sludge loading station, chemical and odor control systems



# Overall Comparison of Optimization

## ■ Before Upgrade w/o Incinerator

- Co-Settling Gravity Thickeners
  - Minimal thickening 1.5-3% Solids
  - No contract for disposal
- Belt Filter Presses
  - Redundant unit out of service
  - No contract for disposal
- Hauling both liquid **AND** cake for disposal
  - Average liquid hauling **10-12 trucks** per day **AND**
  - Average cake hauling **2 trailers** per week


## ■ Basis of Design Upgrade

- Gravity Thickeners
  - Primary sludge to 4.5% solids
- Gravity Belt Thickeners
  - WAS sludge to 5% solids
- Belt Filter Presses
  - Combined thickened sludge to 25% cake
- Hauling liquid **OR** cake disposal
  - Primarily cake disposal (liquid as backup)
    - Average **3 trailers** per week






# Operations





# GBT and BFP Startup

- Gravity Thickeners were not ready yet, so had to change some valve positions and install temporary piping to allow for co-blending of primary sludge with TWAS for dewatering.
- Cake started off at 20%, but then when GT's were started up, 28-30% cake.
- Where to bring 3,600 dry tons/year of cake?







# Disposal Decision

- Inframark researched options for disposal of sludge cake resulting in agreement with Synagro's EPIC division.
- Sludge cake is trucked to Westborough, MA, then put on rail to the Tunnel Hill Reclamation Landfill in Ohio.
- Fall River was 1<sup>st</sup> in region to implement this solution.



# Equipment Tweaks

- Raise screw spreader a few inches to get trailer/bin to fit.
- Extended chute over spreader to reach shorter bins.
- Cake was getting hung up, so we increased the angle of BFP chute.





# Safety First

- Needed to access top of bin to remove covers, so:
- Purchased scaffolding from HD and creatively assembled so operators can remove cover safely and efficiently.
- Liner installed in bin to ensure smooth exodus of cake when dumping at landfill.



# Add-Ons

- As a result of successful cake disposal program, Fall River increased the scope:
- Built a vector dump pad allowing for all collection system debris to go to EPIC.
- Including grit and rag bins from the headworks operation.







# Questions & Discussion



City of Fall River Solids Handling Optimization

