

# Cortland, NY Anaerobic Digestion Improvements


From Antiquated to Updated and Ready for Yogurt

**WESTECH**  
*Process Equipment. Process Driven.*

Presented by:  
Matthew Williams  
mwilliams@westech-inc.com  
WesTech Engineering, Inc.  
27 October 2017

# Cortland, NY WWTP

- Serves Cortland, Homer, McGraw and a portion of Cortlandville
- Funding through state revolving loan fund CWSRF, with an additional \$2 million grant for a digester and CHP
- They had to upgrade to meet Chesapeake Bay nutrient requirements



# The Phases of Change

- **Phase 1:** Solids Handling Deficiencies
- **Phase 2:** Installing SBR and replacing the antiquated SCADA system
- **Phase 3:** Digesters and CHP



# Wooring Industry

- Historically lost thousands of manufacturing jobs
- Needed new development
- Offered a renovation opportunity for the WWTP



# Yogurt Necessitates Change

- Acidic whey needed disposal.
- Existing system couldn't handle the additional load plus future growth.
- A quick and forward-thinking solution was needed.
- This all happened during Phase 3.



# Old Milk is Bad Milk

- Old steel fixed & floating covers (36' diameter)
- Gas mixing system (red compressor house)
- 75-year-old digester complex







## Tight Quarters

- Spiral Heat Exchangers upstairs
- Pumps downstairs
- Digester building was very crowded with existing piping and equipment.





# Mixing Improvements



- Could not add mixing equipment to digester building.
- Needed something aggressive that would minimize foaming.
- Internal and External Mechanical Draft Tube mixers were selected.
- Reliable Operation 10+ years expected before rebuild, 5-year guarantee.



# Draft Tube Mechanical Digester Mixers




# New Digester Covers & Gas Storage

- 36' dia. Dual Membrane Gasholder provided more gas storage
- (2) 36' dia. Stainless Steel Fixed Covers



# Working Through Design While Purchasing

- The plant, engineer, agent and equipment supplier went through design, purchasing and installation quickly so the plant could start receiving whey.



# Where there's a will there's a Whey

- Heat exchanger for the liquid whey holding tank
- Glass-lined to prevent milkstone buildup
- Tank is mixed and whey is fed to digester at ~95 degrees F.
- Heat Exchanger Installation Challenges




# Quality on a Deadline

- Stainless steel fixed covers to work with the timeline
  - No blast or paint
  - Reduced welding
  - Avoiding inspection and repainting
- DuoSphere™ instead of floating steel gasholder cover
  - Quick install (weeks vs. months)
  - More gas storage (~100% more)
  - No annular gap (fully gastight)



# From Cows to Lightbulbs

- Next phase will add CHP
- Larger than previously planned due to high-strength waste.
- Project will provide significant savings.





# Creating New Jobs and Great yogurt

- Goal is to put the city in a competitive economic position to attract more jobs
- The facility is now able to treat 9 MGD more sustainably.



# Thank You & Questions

Matthew Williams  
mwilliams@westech-inc.com  
801-803-4912  
WesTech Engineering, Inc.

**WESTECH**  
*Process Equipment. Process Driven.*