



New Salem Street Culvert Replacement

A Unique Solution to a Culvert Replacement
on Poor Soils

ENVIRONMENTAL
 PARTNERS

PRESENTERS



Ryan J. Paul, PE
Project Manager
rjp@envpartners.com



Maria E. George, PE
PROJECT ENGINEER
meg@envpartners.com



ABOUT EP

Environmental Partners (EP) is an award-winning multidisciplinary engineering and consulting firm celebrating its 25th year in business.

EP provides a broad range of services to municipal, commercial, industrial, and institutional clients.

SERVICES INCLUDE

Civil Engineering

Construction Management

Drinking Water

Emergency Management Services

Owner's Project Management (OPM)

Environmental


Infrastructure Asset Management

Planning

Stormwater




Traffic & Transportation

Wastewater



Project Location

New Salem Street, Wakefield MA




480 FT Culvert
across parking lots
Corrugated Metal Arch



Sinkhole Late 2019



Profile – Sagging Pipe



Submerged Outlet and Sediment



Mill River – Tailwater




STORMWATER MODEL AND CULVERT SIZING

Culvert Design Parameters

- Tailwater Condition
- Flood zone – flooding may occur due to Mill River Flooding
- Shallow Bury – cover depth ranges from 1-foot to 3-feet
- Basis of design:
 - Connect drainage channels with new culvert. Culvert should not be the cause of backed up flow
 - Stabilize parking lot/roadway above the culvert
- Model
 - PCSWMM – dynamic modeling
 - Constant tailwater assumed – Mill River not modeled



PCSWMM Model



Existing Model



Proposed Model

Culvert Selection


Culvert: 4' Wide by 3' Deep by 480' Long Culvert

- Depth based on tailwater and existing surface.


Headwall: Based on existing elevations and side slopes

Material: Reinforced Concrete

- Shallow bury required robust material for H-20 Loading.



Drawings by Concrete Systems, Inc.




Drawings by Concrete Systems, Inc.




CULVERT FOUNDATION DESIGN

Unstable Subsurface Conditions




Foundation Design Loads



- Peat Soil Bearing Capacity: > 0.5 -tsf
- Live Load: 16-Kip Load at Culvert Joint
- Dead Load: 1.5-Kip/ft over 8' (or 14-kips at center)
- Working Load: 30-kips
- Ultimate Load: 30-kips x 2.0 Factor of Safety = 60-kips



Initial Helical Pile Design

- “A.B. Chance” Piles Selected;
- 2x Helical Piles per joint;
- 132 total piles;
- Average depth of pile: 30'
- Working Load per Pile: 15-kip;
- Ult. Load Req. per Pile: 30-kip (2.0 SF);
- Torque Req.: 3,400-ft-lbs.




Helical Pile Beam Design

- Piles Embedded in 16" x 16" concrete grade beam;
- 63 Total Grade Beams;
- 2 large end beams for culvert headwalls with 4-embedded piles.



Helical Pile Installation




Helical Pile Load Testing

- 2 Pile Tests Conducted to verify design.
- Piles did not reach torque requirement in sand layer.
- Most piles required installation into refusal layer to reach load requirements.



Construction Phasing



Construction (Phase 1)




Construction (Phase 1)



Issues During Construction

- Obstacles during pile install (boulders, and old foundation);
- No torque resistance in sand layer;
- Roof drains and existing drainage not on record;
- Weather during winter and early spring.



SOIL ABATEMENT




Soil Abatement

- EP conducted pre-characterization of the site
 - VOC's and Petroleum Hydrocarbons were present
- Work performed under MassDEP Utility-Related Abatement Measure (or URAM)
- Soil was not able to be reused on site and was required to be sent to an appropriate soil handling facility



Soil Management During Construction

- All soil was stockpiled at a Wakefield DPW Yard (Waiver accepted from MassDEP);
- Soil separated based on field observations and EP pre-characterization;
- Small concentrations of PCB's and Hydrocarbons found.



Drone imagery by Onyx Corporation

Aroclor 1262	1			mg/kg	0.04	U	0.19	U	0.0427	U	0.0436	U
Aroclor 1268	1			mg/kg	0.04	U	0.19	U	0.0427	U	0.0436	U
PCBs, Total	1			mg/kg	0.04	U	0.637		0.109		0.0685	
MCP Semivolatile Organics												
Acenaphthene	4	4	5	mg/kg	0.3		0.16	U	0.17	U	0.18	U
1,2,4-Trichlorobenzene				mg/kg	0.2	U	0.2	U	0.22	U	0.23	U
Hexachlorobenzene	0.7			mg/kg	0.085	U	0.084	U	0.091	U	0.097	U
1,4-Dioxane				mg/kg	0.077	U	0.084	U	0.11	U	0.09	U
Total VOCs			4	10 mg/kg	0.0308		ND		ND		0.141	
Petroleum Hydrocarbon Quantitation												
TPH (C10-C38)	1000		2500	5000 mg/kg	689		577		464		343	

* Comparison is not performed on parameters with non-numeric criteria




Final Soil Disposal

- Currently 5-piles of utility trench soil material stockpiled
- Total Soil Stockpiled: Approximately 2,000-cy
- Soil was categorized as “Impacted Soil,” but did not exceed MassDEP RSC-1 contaminant levels.
- All soil is anticipated to be hauled to a lined landfill by the end of June 2021.



Final Completed Project



- 480 LF of Culvert
- Headwalls and Wingwalls
- Local drainage
- Wetland Replication



Final Construction Photos



Permitting Summary

- Conservation Commission Notice of Intent
- Army Corps of Engineers (USACE) MA General Permit
- URAM – Soil Disposal
 - Submitted by Contractor's LSP before construction
 - Details handling, storage, and disposal plan




Construction Costs Summary

Culvert	\$718,000
Helical Piles and Grade Beams	\$190,000
Soil Disposal	\$142,000
<u>Local Drainage System</u>	<u>\$180,000</u>
Total	\$1,230,000



THANK YOU



ENVIRONMENTAL
 PARTNERS

Acknowledgements

- Joseph Conway – Town of Wakefield DPW Superintendent
- William Renault, PE - Town of Wakefield Engine
- Onyx Corporation – General Contractor
- All Environmental Partners Staff

